














































































































































PETE'S WAY EXTENSION


CITY OF WARNER ROBINS , GEORGIA

JULY, 2024

REVISED 03/19/2025

SITE PROJECT DATA	ZONING REQUIREMENTS	⑤ OWNER/PRIMARY PERMITTEE	PROJECT ENGINEER CONTACT	SURVEYOR	UTILITY NOTES																																																																																																																									
<p>PROJECT ADDRESS: PETE'S WAY @ CRESTVIEW CHURCH ROAD EXTENDED TO GA. HWY 247C.</p> <p>TOTAL SITE AREA = 362.53 AC. TOTAL DISTURBED AREA = 9.69 AC.</p> <p>STREET DESIGN STANDARDS: RIGHT OF WAY WIDTH = 120' TOTAL STREET LENGTH = 3520' ROAD WIDTH = 30'</p>	N/A	JOINT DEVELOPMENT AUTHORITY OF PEACH COUNTY & CIY OF WARNER ROBINS 425 JAMES E. KHOURY DRIVE FORT VALLEY 478-825-3826 EMAIL: bj-walker@peachcounty.net	CHAD BRYANT, P.E. PRESIDENT BRYANT ENGINEERING 111 PERIMETER ROAD, SUITE A PERRY, GA 31069 OFFICE: (478) 224-7070 FAX: (478) 224-7072 EMAIL: chad@bryantengllc.com	MARTY McLEOD, R.L.S. MCLEOD SURVEYING, LLC. 111 PERIMETER ROAD, SUITE A PERRY, GA 31069 (478) 224-7070	<div><p>*ALL UTILITIES, STORM DRAINS AND SERVICE LINES WILL BE MARKED WITH LOCATOR WIRE</p><p>*ALL WATER AND SEWER INSTALLATIONS SHALL CONFORM TO THE CITY OF WARNER ROBINS UTILITY DEPARTMENT WATER, SEWER, AND GAS STANDARDS, LATEST EDITION</p></div> <div><p>THE EXISTING UTILITIES SHOWN ON THIS PLAN WERE OBTAINED FROM VARIOUS UTILITY COMPANIES, VARIOUS GOVERNMENTAL AGENCIES, AND ABOVE GROUND OBSERVATION. THE SURVEYOR AND/OR ENGINEER MAKE NO CLAIM TO THE COMPLETENESS OF THIS INFORMATION. THE SIZE, LOCATION, OR ADDITIONAL UTILITIES MAY BE UNCOVERED UPON EXCAVATION. PRIOR TO BEGINNING ANY EARTH DISTURBING ACTIVITIES, THE UTILITY PROTECTION SERVICE FOR THIS AREA MUST BE NOTIFIED.</p><div><p>IF YOU DIG GEORGIA ... CALL US FIRST UTILITIES PROTECTION CENTER STATE WIDE 1 800 282-7411 IT'S THE LAW</p></div></div>																																																																																																																									
LEGEND																																																																																																																														
<table><tr><th>ABBREVIATION</th><th>DESCRIPTION</th></tr><tr><td>IPS</td><td>IRON PIN SET</td></tr><tr><td>IPF</td><td>IRON PIN FOUND</td></tr><tr><td>R/W</td><td>RIGHT OF WAY</td></tr><tr><td>BSL</td><td>BUILDING SETBACK LINE</td></tr><tr><td>PL</td><td>PROPERTY LINE</td></tr><tr><td>DE</td><td>DRAINAGE EASEMENT</td></tr><tr><td>SSE</td><td>SANITARY SEWER EASEMENT</td></tr><tr><td>MH</td><td>MANHOLE</td></tr><tr><td>CB</td><td>CATCH BASIN</td></tr><tr><td>DWCB</td><td>DOUBLE WING CATCH BASIN</td></tr><tr><td>SWCB</td><td>SINGLE WING CATCH BASIN</td></tr><tr><td>JB</td><td>JUNCTION BOX</td></tr><tr><td>DI</td><td>DROP INLET</td></tr><tr><td>GI</td><td>GRATE INLET</td></tr><tr><td>HW</td><td>HEADWALL</td></tr><tr><td>YI</td><td>YARD INLET</td></tr><tr><td>SES</td><td>SAFETY END SECTION</td></tr><tr><td>FES</td><td>FLARED END SECTION</td></tr><tr><td>AC</td><td>ACRE</td></tr><tr><td>EP</td><td>EDGE PAVEMENT</td></tr><tr><td>BC</td><td>BACK OF CURB</td></tr><tr><td>CRK</td><td>CREEK</td></tr></table>	ABBREVIATION	DESCRIPTION	IPS	IRON PIN SET	IPF	IRON PIN FOUND	R/W	RIGHT OF WAY	BSL	BUILDING SETBACK LINE	PL	PROPERTY LINE	DE	DRAINAGE EASEMENT	SSE	SANITARY SEWER EASEMENT	MH	MANHOLE	CB	CATCH BASIN	DWCB	DOUBLE WING CATCH BASIN	SWCB	SINGLE WING CATCH BASIN	JB	JUNCTION BOX	DI	DROP INLET	GI	GRATE INLET	HW	HEADWALL	YI	YARD INLET	SES	SAFETY END SECTION	FES	FLARED END SECTION	AC	ACRE	EP	EDGE PAVEMENT	BC	BACK OF CURB	CRK	CREEK	<table><tr><th>ABBREVIATION</th><th>DESCRIPTION</th></tr><tr><td>L.L.L.</td><td>LAND LOT LINE</td></tr><tr><td>FH</td><td>FIRE HYDRANT</td></tr><tr><td>-X-</td><td>FENCE LINE</td></tr><tr><td>FEE</td><td>FINISH FLOOR ELEVATION</td></tr><tr><td>-P-</td><td>POWER LINE</td></tr><tr><td>PP</td><td>POWER POLE</td></tr><tr><td>CL</td><td>CENTER LINE</td></tr><tr><td>TH</td><td>TEST HOLE</td></tr><tr><td>SPED</td><td>SITE PLAN ENG. DEPT.</td></tr><tr><td>SPHD</td><td>SITE PLAN HEALTH DEPT.</td></tr><tr><td>R=</td><td>RADIUS</td></tr><tr><td>EL</td><td>ELEVATION</td></tr><tr><td>INV</td><td>INVERT</td></tr><tr><td>RDP</td><td>RESIDENTIAL DRAINAGE PLAN</td></tr><tr><td>RCP</td><td>REINFORCED CONCRETE PIPE</td></tr><tr><td>CMP</td><td>CORRUGATED METAL PIPE</td></tr><tr><td>HDPE</td><td>HIGH DENSITY POLYETHYLENE PIPE</td></tr><tr><td>LP</td><td>LIGHT POLE</td></tr><tr><td>WV</td><td>WATER VALVE</td></tr><tr><td>WM</td><td>WATER METER</td></tr><tr><td>△</td><td>REVISION NUMBERS</td></tr></table>	ABBREVIATION	DESCRIPTION	L.L.L.	LAND LOT LINE	FH	FIRE HYDRANT	-X-	FENCE LINE	FEE	FINISH FLOOR ELEVATION	-P-	POWER LINE	PP	POWER POLE	CL	CENTER LINE	TH	TEST HOLE	SPED	SITE PLAN ENG. DEPT.	SPHD	SITE PLAN HEALTH DEPT.	R=	RADIUS	EL	ELEVATION	INV	INVERT	RDP	RESIDENTIAL DRAINAGE PLAN	RCP	REINFORCED CONCRETE PIPE	CMP	CORRUGATED METAL PIPE	HDPE	HIGH DENSITY POLYETHYLENE PIPE	LP	LIGHT POLE	WV	WATER VALVE	WM	WATER METER	△	REVISION NUMBERS	<table><tr><th>ABBREVIATION</th><th>DESCRIPTION</th></tr><tr><td>PIV</td><td>POST INDICATOR VALVE</td></tr><tr><td>FDC</td><td>FIRE DEPARTMENT CONNECTION</td></tr><tr><td>SS</td><td>SANITARY SEWER</td></tr><tr><td>Mp</td><td>MONITORING POINT</td></tr><tr><td>Np</td><td>SAMPLING POINT</td></tr><tr><td>N/F</td><td>NOW OR FORMERLY</td></tr><tr><td>OCS</td><td>OUTLET CONTROL STRUCTURE</td></tr><tr><td>WQ</td><td>WATER QUALITY</td></tr><tr><td>CP</td><td>CHANNEL PROTECTION</td></tr><tr><td>WSE</td><td>WATER SURFACE ELEVATION</td></tr><tr><td>WSA</td><td>WATER SURFACE AREA</td></tr></table> <div><p>WETLANDS</p><table><tr><td>P</td><td>PALUSTRINE</td></tr><tr><td>FO</td><td>FORESTED</td></tr><tr><td>I</td><td>BROAD LEAFED DECIDUOUS</td></tr><tr><td>A</td><td>TEMPORARILY FLOODED</td></tr><tr><td>★</td><td>CRITICAL SLOPE AREA</td></tr></table></div>	ABBREVIATION	DESCRIPTION	PIV	POST INDICATOR VALVE	FDC	FIRE DEPARTMENT CONNECTION	SS	SANITARY SEWER	Mp	MONITORING POINT	Np	SAMPLING POINT	N/F	NOW OR FORMERLY	OCS	OUTLET CONTROL STRUCTURE	WQ	WATER QUALITY	CP	CHANNEL PROTECTION	WSE	WATER SURFACE ELEVATION	WSA	WATER SURFACE AREA	P	PALUSTRINE	FO	FORESTED	I	BROAD LEAFED DECIDUOUS	A	TEMPORARILY FLOODED	★	CRITICAL SLOPE AREA
ABBREVIATION	DESCRIPTION																																																																																																																													
IPS	IRON PIN SET																																																																																																																													
IPF	IRON PIN FOUND																																																																																																																													
R/W	RIGHT OF WAY																																																																																																																													
BSL	BUILDING SETBACK LINE																																																																																																																													
PL	PROPERTY LINE																																																																																																																													
DE	DRAINAGE EASEMENT																																																																																																																													
SSE	SANITARY SEWER EASEMENT																																																																																																																													
MH	MANHOLE																																																																																																																													
CB	CATCH BASIN																																																																																																																													
DWCB	DOUBLE WING CATCH BASIN																																																																																																																													
SWCB	SINGLE WING CATCH BASIN																																																																																																																													
JB	JUNCTION BOX																																																																																																																													
DI	DROP INLET																																																																																																																													
GI	GRATE INLET																																																																																																																													
HW	HEADWALL																																																																																																																													
YI	YARD INLET																																																																																																																													
SES	SAFETY END SECTION																																																																																																																													
FES	FLARED END SECTION																																																																																																																													
AC	ACRE																																																																																																																													
EP	EDGE PAVEMENT																																																																																																																													
BC	BACK OF CURB																																																																																																																													
CRK	CREEK																																																																																																																													
ABBREVIATION	DESCRIPTION																																																																																																																													
L.L.L.	LAND LOT LINE																																																																																																																													
FH	FIRE HYDRANT																																																																																																																													
-X-	FENCE LINE																																																																																																																													
FEE	FINISH FLOOR ELEVATION																																																																																																																													
-P-	POWER LINE																																																																																																																													
PP	POWER POLE																																																																																																																													
CL	CENTER LINE																																																																																																																													
TH	TEST HOLE																																																																																																																													
SPED	SITE PLAN ENG. DEPT.																																																																																																																													
SPHD	SITE PLAN HEALTH DEPT.																																																																																																																													
R=	RADIUS																																																																																																																													
EL	ELEVATION																																																																																																																													
INV	INVERT																																																																																																																													
RDP	RESIDENTIAL DRAINAGE PLAN																																																																																																																													
RCP	REINFORCED CONCRETE PIPE																																																																																																																													
CMP	CORRUGATED METAL PIPE																																																																																																																													
HDPE	HIGH DENSITY POLYETHYLENE PIPE																																																																																																																													
LP	LIGHT POLE																																																																																																																													
WV	WATER VALVE																																																																																																																													
WM	WATER METER																																																																																																																													
△	REVISION NUMBERS																																																																																																																													
ABBREVIATION	DESCRIPTION																																																																																																																													
PIV	POST INDICATOR VALVE																																																																																																																													
FDC	FIRE DEPARTMENT CONNECTION																																																																																																																													
SS	SANITARY SEWER																																																																																																																													
Mp	MONITORING POINT																																																																																																																													
Np	SAMPLING POINT																																																																																																																													
N/F	NOW OR FORMERLY																																																																																																																													
OCS	OUTLET CONTROL STRUCTURE																																																																																																																													
WQ	WATER QUALITY																																																																																																																													
CP	CHANNEL PROTECTION																																																																																																																													
WSE	WATER SURFACE ELEVATION																																																																																																																													
WSA	WATER SURFACE AREA																																																																																																																													
P	PALUSTRINE																																																																																																																													
FO	FORESTED																																																																																																																													
I	BROAD LEAFED DECIDUOUS																																																																																																																													
A	TEMPORARILY FLOODED																																																																																																																													
★	CRITICAL SLOPE AREA																																																																																																																													
<table><tr><th>SYMBOL</th><th>DESCRIPTION</th></tr><tr><td></td><td>EXISTING CATCH BASIN</td></tr><tr><td></td><td>EXISTING YARD INLET</td></tr><tr><td></td><td>EXISTING GRATE INLET</td></tr><tr><td></td><td>EXISTING HEADWALL</td></tr><tr><td></td><td>EXISTING DRAINAGE PIPE</td></tr><tr><td></td><td>EXISTING SAFETY END SECTION</td></tr><tr><td></td><td>EXISTING SANITARY SEWER MANHOLE</td></tr><tr><td></td><td>EXISTING SANITARY SEWER LINE</td></tr><tr><td></td><td>EXISTING WATER MAIN</td></tr><tr><td></td><td>EXISTING WATER VALVE & BOX</td></tr><tr><td></td><td>EXISTING CROSS</td></tr><tr><td></td><td>EXISTING TEE</td></tr><tr><td></td><td>EXISTING REDUCER</td></tr><tr><td></td><td>EXISTING PLUG</td></tr><tr><td></td><td>EXISTING BLOW-OFF</td></tr><tr><td></td><td>EXISTING FIRE HYDRANT</td></tr><tr><td></td><td>EXISTING WATER METER</td></tr><tr><td></td><td>EXISTING BOUNDARY/RW LINE</td></tr><tr><td></td><td>EXISTING LOT LINE</td></tr><tr><td></td><td>EXISTING LOT NUMBER</td></tr><tr><td></td><td>EXISTING BLOCK NUMBER</td></tr><tr><td></td><td>LAND LOT NUMBER</td></tr><tr><td></td><td>EXISTING OVERHEAD POWER LINE</td></tr><tr><td></td><td>EXISTING POWER POLE</td></tr><tr><td></td><td>EXISTING CONTOUR</td></tr></table>	SYMBOL	DESCRIPTION		EXISTING CATCH BASIN		EXISTING YARD INLET		EXISTING GRATE INLET		EXISTING HEADWALL		EXISTING DRAINAGE PIPE		EXISTING SAFETY END SECTION		EXISTING SANITARY SEWER MANHOLE		EXISTING SANITARY SEWER LINE		EXISTING WATER MAIN		EXISTING WATER VALVE & BOX		EXISTING CROSS		EXISTING TEE		EXISTING REDUCER		EXISTING PLUG		EXISTING BLOW-OFF		EXISTING FIRE HYDRANT		EXISTING WATER METER		EXISTING BOUNDARY/RW LINE		EXISTING LOT LINE		EXISTING LOT NUMBER		EXISTING BLOCK NUMBER		LAND LOT NUMBER		EXISTING OVERHEAD POWER LINE		EXISTING POWER POLE		EXISTING CONTOUR	<table><tr><th>SYMBOL</th><th>DESCRIPTION</th></tr><tr><td></td><td>PROPOSED OUTLET CONTROL STRUCTURE</td></tr><tr><td></td><td>PROPOSED DOT 1034D</td></tr><tr><td></td><td>PROPOSED DOT 1033D</td></tr><tr><td></td><td>PROPOSED CATCH BASIN</td></tr><tr><td></td><td>PROPOSED YARD INLET</td></tr><tr><td></td><td>PROPOSED GRATE INLET</td></tr><tr><td></td><td>PROPOSED HEADWALL</td></tr><tr><td></td><td>PROPOSED HIGH/LOW POINT</td></tr><tr><td></td><td>PROPOSED DRAINAGE PIPE</td></tr><tr><td></td><td>PROPOSED DRAINAGE FLOW ARROW</td></tr><tr><td></td><td>PROPOSED SAFETY END SECTION</td></tr><tr><td></td><td>PROPOSED SANITARY SEWER MANHOLE</td></tr><tr><td></td><td>PROPOSED SANITARY SEWER LINE</td></tr><tr><td></td><td>PROPOSED WATER VALVE & BOX</td></tr><tr><td></td><td>PROPOSED CROSS</td></tr><tr><td></td><td>PROPOSED TEE</td></tr><tr><td></td><td>PROPOSED REDUCER</td></tr><tr><td></td><td>PROPOSED PLUG</td></tr><tr><td></td><td>PROPOSED BLOW-OFF</td></tr><tr><td></td><td>PROPOSED FIRE HYDRANT</td></tr><tr><td></td><td>PROPOSED WATER METER</td></tr><tr><td></td><td>PROPOSED WATER MAIN</td></tr><tr><td></td><td>PROPOSED BOUNDARY/RW LINE</td></tr><tr><td></td><td>PROPOSED LOT LINE</td></tr><tr><td></td><td>PROPOSED LOT NUMBER</td></tr><tr><td></td><td>PROPOSED BLOCK NUMBER</td></tr><tr><td></td><td>PROPOSED CONTOUR</td></tr><tr><td></td><td>PROPOSED TREE FENCE</td></tr><tr><td></td><td>PROPOSED SILT FENCE</td></tr></table>	SYMBOL	DESCRIPTION		PROPOSED OUTLET CONTROL STRUCTURE		PROPOSED DOT 1034D		PROPOSED DOT 1033D		PROPOSED CATCH BASIN		PROPOSED YARD INLET		PROPOSED GRATE INLET		PROPOSED HEADWALL		PROPOSED HIGH/LOW POINT		PROPOSED DRAINAGE PIPE		PROPOSED DRAINAGE FLOW ARROW		PROPOSED SAFETY END SECTION		PROPOSED SANITARY SEWER MANHOLE		PROPOSED SANITARY SEWER LINE		PROPOSED WATER VALVE & BOX		PROPOSED CROSS		PROPOSED TEE		PROPOSED REDUCER		PROPOSED PLUG		PROPOSED BLOW-OFF		PROPOSED FIRE HYDRANT		PROPOSED WATER METER		PROPOSED WATER MAIN		PROPOSED BOUNDARY/RW LINE		PROPOSED LOT LINE		PROPOSED LOT NUMBER		PROPOSED BLOCK NUMBER		PROPOSED CONTOUR		PROPOSED TREE FENCE		PROPOSED SILT FENCE													
SYMBOL	DESCRIPTION																																																																																																																													
	EXISTING CATCH BASIN																																																																																																																													
	EXISTING YARD INLET																																																																																																																													
	EXISTING GRATE INLET																																																																																																																													
	EXISTING HEADWALL																																																																																																																													
	EXISTING DRAINAGE PIPE																																																																																																																													
	EXISTING SAFETY END SECTION																																																																																																																													
	EXISTING SANITARY SEWER MANHOLE																																																																																																																													
	EXISTING SANITARY SEWER LINE																																																																																																																													
	EXISTING WATER MAIN																																																																																																																													
	EXISTING WATER VALVE & BOX																																																																																																																													
	EXISTING CROSS																																																																																																																													
	EXISTING TEE																																																																																																																													
	EXISTING REDUCER																																																																																																																													
	EXISTING PLUG																																																																																																																													
	EXISTING BLOW-OFF																																																																																																																													
	EXISTING FIRE HYDRANT																																																																																																																													
	EXISTING WATER METER																																																																																																																													
	EXISTING BOUNDARY/RW LINE																																																																																																																													
	EXISTING LOT LINE																																																																																																																													
	EXISTING LOT NUMBER																																																																																																																													
	EXISTING BLOCK NUMBER																																																																																																																													
	LAND LOT NUMBER																																																																																																																													
	EXISTING OVERHEAD POWER LINE																																																																																																																													
	EXISTING POWER POLE																																																																																																																													
	EXISTING CONTOUR																																																																																																																													
SYMBOL	DESCRIPTION																																																																																																																													
	PROPOSED OUTLET CONTROL STRUCTURE																																																																																																																													
	PROPOSED DOT 1034D																																																																																																																													
	PROPOSED DOT 1033D																																																																																																																													
	PROPOSED CATCH BASIN																																																																																																																													
	PROPOSED YARD INLET																																																																																																																													
	PROPOSED GRATE INLET																																																																																																																													
	PROPOSED HEADWALL																																																																																																																													
	PROPOSED HIGH/LOW POINT																																																																																																																													
	PROPOSED DRAINAGE PIPE																																																																																																																													
	PROPOSED DRAINAGE FLOW ARROW																																																																																																																													
	PROPOSED SAFETY END SECTION																																																																																																																													
	PROPOSED SANITARY SEWER MANHOLE																																																																																																																													
	PROPOSED SANITARY SEWER LINE																																																																																																																													
	PROPOSED WATER VALVE & BOX																																																																																																																													
	PROPOSED CROSS																																																																																																																													
	PROPOSED TEE																																																																																																																													
	PROPOSED REDUCER																																																																																																																													
	PROPOSED PLUG																																																																																																																													
	PROPOSED BLOW-OFF																																																																																																																													
	PROPOSED FIRE HYDRANT																																																																																																																													
	PROPOSED WATER METER																																																																																																																													
	PROPOSED WATER MAIN																																																																																																																													
	PROPOSED BOUNDARY/RW LINE																																																																																																																													
	PROPOSED LOT LINE																																																																																																																													
	PROPOSED LOT NUMBER																																																																																																																													
	PROPOSED BLOCK NUMBER																																																																																																																													
	PROPOSED CONTOUR																																																																																																																													
	PROPOSED TREE FENCE																																																																																																																													
	PROPOSED SILT FENCE																																																																																																																													
VICINITY MAP ⑩																																																																																																																														
																																																																																																																														
VICINITY MAP N.T.S.																																																																																																																														

Sheet Number	Sheet Title
C-0.1	COVER SHEET
C-0.2	GENERAL NOTES
C-1.1	EXISTING CONDITIONS
C-2.0	OVERALL ROAD ALIGNMENT
C-2.1	OVERALL ROAD DITCH BASIN MAP
C-2.2	PLAN AND PROFILE
C-2.3	PLAN AND PROFILE
C-2.4	PLAN AND PROFILE
C-2.5	RIGHT-OF-WAY, STRIPING PLAN, & SIGNAGE PLAN
C-2.6	RIGHT-OF-WAY, STRIPING PLAN & SIGNAGE PLAN
C-3.1	GRADING & DRAINAGE PLAN
C-3.2	GRADING & DRAINAGE PLAN
C-3.3	DRAINAGE PROFILES
C-3.4	CROSS SECTIONS
C-3.5	CROSS SECTIONS
C-3.6	CROSS SECTIONS
C-3.7	CROSS SECTIONS
C-3.8	CROSS SECTIONS
C-4.1	UTILITY PLAN
C-4.2	UTILITY PLAN
C-4.3	SANITARY SEWER PROFILES
C-4.4	SANITARY SEWER PROFILES
C-5.1	EROSION CONTROL PLAN
C-5.2	EROSION CONTROL PLAN
C-5.4	EROSION CONTROL NARRATIVE
C-5.5	NPDES PERMIT No. GAR100002
C-5.6	EROSION CONTROL DETAILS
C-6.1	SEWER DETAILS
C-6.2	WATER DETAILS
C-6.3	MISCELLANEOUS DETAILS



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING

phone: (478) 224-7070 • fax: (478) 224-7072
111 Perimeter Road, Suite A
Perry, Georgia 31069

www.bryantengllc.com

COUNTY: HOUSTON
LL/DISTRICT: 03/5
DWG: 0322-002-MASTER
DATE: 7/10/24
SCALE: 1"= 50'
JOB NO.: 0322-002

COVER SHEET FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS

REVISIONS
NO. DATE DESCRIPTION

SHEET NO.
C-0.1

1. STAKING DIMENSIONS ARE MEASURED TO AND FROM EDGE OF PAVEMENT TO PAVEMENT.
2. ANY AND ALL DAMAGE TO EXISTING ASPHALT OR CONCRETE PAVEMENT DESIGNATED TO REMAIN, WHICH RESULTS FROM THE NEW CONSTRUCTION SHALL BE REPLACED WITH LIKE MATERIAL AT THE CONTRACTORS EXPENSE AND TO THE SATISFACTION OF THE ENGINEER.
3. THE CONTRACTOR MUST IDENTIFY ANY PRE-EXISTING DAMAGE TO ANY PAVEMENTS TO REMAIN PRIOR TO STARTING ANY WORK. THE PRE-EXISTING DAMAGE MUST BE REPORTED TO THE OWNER IN WRITING BEFORE ANY WORK IS STARTED. IF NO DAMAGE IS IDENTIFIED, THEN THE PAVEMENTS WILL BE CONSIDERED TO BE IN GOOD CONDITION AND UNDAMAGED.
4. THE CONTRACTOR SHALL NOT DISTURB ANY UTILITY WITHOUT THE PRIOR APPROVAL OF THE UTILITY OWNER.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COMPLYING WITH ALL FEDERAL, STATE, AND LOCAL CODES, LAWS, AND REGULATIONS AND SHALL VERIFY AND OBTAIN NECESSARY PERMITS REQUIRED FOR CONSTRUCTION INCLUDING POLLUTION CONTROL PERMITS PRIOR TO COMMENCEMENT OF CONSTRUCTION ACTIVITIES.
6. THE CONTRACTOR SHALL KEEP ALL PAVED SURFACES CLEAN AND FREE OF MUD AND DEBRIS.
7. NOTHING IN THE GENERAL NOTES OF CONSTRUCTION DOCUMENTS SHALL RELIEVE THE CONTRACTOR FROM HIS RESPONSIBILITIES TOWARD THE SAFETY AND CONVENIENCE OF THE GENERAL PUBLIC.
8. THE CONTRACTOR SHALL FIELD VERIFY ALL TIE-INS. ANY DIFFERENCE ENCOUNTERED SHALL BE BROUGHT TO THE ENGINEERS ATTENTION IMMEDIATELY.
9. SPOT ELEVATIONS SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO CURB AND GUTTER INSTALLATION AND FINAL PAVEMENT INSTALLATION.
10. ANY CONFLICTS RESULTING FROM THE SPOT ELEVATIONS SHOWN ON THIS PLAN SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR PERFORMING THE WORK SPECIFIC TO CURB AND GUTTER, SIDEWALK AND ASPHALT BASE AND PAVING.
11. ALL WORK SHALL BE IN ACCORDANCE WITH COUNTY/CITY STANDARDS AND SPECIFICATIONS.
12. CONTRACTOR SHALL HAVE ALL PERIMETER EROSION CONTROL MEASURES IN PLACE PRIOR TO CONSTRUCTION.
13. CONTRACTOR TO VERIFY ALL HORIZONTAL & VERTICAL LOCATIONS OF ALL EXISTING AND PROPOSED STRUCTURES PRIOR TO CONSTRUCTION.
14. CONTRACTOR TO PROVIDE ALL CONSTRUCTION STAKING.
15. ALL EXTENSIONS AND ADDITIONS TO THE COUNTY/CITY UTILITY SYSTEM WILL BE PERFORMED BY A GEORGIA LICENSED UTILITY CONTRACTOR.
16. ALL CONCRETE SLABS, DRAINAGE STRUCTURES, DRAINAGE PIPES AND OTHER DEBRIS REMOVED SHALL BE DISPOSED OF OFF SITE.

1. THE CONTRACTOR WILL PROVIDE ALL NECESSARY PROTECTIVE MEASURES TO SAFEGUARD EXISTING UTILITIES FROM DAMAGE DURING CONSTRUCTION OF THIS PROJECT. IN THE EVENT THAT SPECIAL EQUIPMENT IS REQUIRED TO WORK OVER AND AROUND THE UTILITIES, THE CONTRACTOR SHALL FURNISH SUCH EQUIPMENT. THE COST OF PROTECTING UTILITIES FROM DAMAGE AND FURNISHING SPECIAL EQUIPMENT SHALL BE INCLUDED IN THE CONTRACTOR'S BID.
2. THE CONTRACTOR SHALL VERIFY EXACT ROUTING AND LOCATION OF ALL EXISTING UTILITIES (SEWER, STORM SEWER, UNDERDRAIN, ELECTRICAL DUCTS, ELECTRICAL UTILITY, ETC.) TO BE DEMOLISHED AND/OR TO REMAIN PRIOR TO BEGINNING ANY WORK.
3. THE CONTRACTOR SHALL VERIFY EXISTING CONDITION SHOWN ON THESE PLANS PRIOR TO BEGINNING ANY CONSTRUCTION OR DEMOLITION.
4. THE CONTRACTOR SHALL VERIFY THE EXISTING INVERT ELEVATIONS OF STORM SEWER AND CULVERTS PRIOR TO BEGINNING CONSTRUCTION.
5. THE CONTRACTOR SHALL TAKE SPECIAL CARE TO PLACE/COMPACT FILL SUFFICIENTLY AROUND AND OVER ALL PIPES, CONDUITS, STRUCTURES, ETC. TO PREVENT SETTLEMENT. ANY SETTLEMENT DURING THE WARRANTY PERIOD SHALL BE RESTORED AND COMPACTED AT NO ADDITIONAL EXPENSE TO THE OWNER.
6. THE EXISTING UTILITIES SHOWN ON THIS PLAN WERE OBTAINED FROM VARIOUS UTILITY COMPANIES, VARIOUS GOVERNMENTAL AGENCIES, AND ABOVE GROUND OBSERVATION. THE SURVEYOR AND/OR ENGINEER MAKE NO CLAIM TO THE COMPLETENESS OF THIS INFORMATION. THE SIZE, LOCATION, OR ADDITIONAL UTILITIES MAY BE UNCOVERED UPON EXCAVATION. PRIOR TO BEGINNING ANY EARTH DISTURBING ACTIVITIES, THE UTILITY PROTECTION SERVICE FOR THIS AREA MUST BE NOTIFIED.

1. CONTRACTOR SHALL VERIFY LOCATION AND DEPTHS OF ALL EXISTING UTILITIES PRIOR TO BEGINNING ANY EXCAVATION (1-800-282-7411).
2. ALL BUILDING AND PAVING SUBGRADE AREAS SHALL BE COMPACTED IN 6" LAYERS TO 98% OF THE MAXIMUM DRY DENSITY AS DETERMINED IN ACCORDANCE WITH ASTM D698, CURRENT EDITION. ALL AREAS SHALL BE PROOFROLLED WITH A 20 TON DUMPTRUCK UNDERCUT ALL AREAS THAT PUMP AND REPLACE WITH A SUITABLE MATERIAL HEREIN SPECIFIED.
3. STORM SEWER PIPING ON SITE SHALL BE EITHER RCP, CMP, OR HDPE. PIPE SHALL MEET THE FOLLOWING REQUIREMENTS:
 - A. RCP - REINFORCED CONCRETE PIPE
PIPE SHALL BE REINFORCED CONCRETE PIPE CONFORMING TO ASTM C76, CLASS III.
 - B. CMP - ALUMINUM CORRUGATED METAL PIPE
PIPE SHALL MEET APPLICABLE REQUIREMENTS OF CURRENT AASHTO SPECIFICATIONS M-196 OR FEDERAL SPECIFICATIONS WW-P-402. PIPE SHALL BE FORMED FROM SHEET CONFORMING TO M-197 ALLOY A/C/AD 3004-H34.
 - C. HDPE - HIGH DENSITY POLYETHYLENE PIPE ADS N-12
POLYETHYLENE PIPE SHALL BE HIGH DENSITY POLYETHYLENE CORRUGATED PIPE WITH AN INTEGRALLY FORMED SMOOTH INTERIOR. PIPE SHALL CONFORM TO REQUIREMENTS OF AASHTO M-294 TYPE S.
4. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE PRINTED SPECIFICATIONS AND REQUIREMENTS.
5. MAXIMUM CUT AND FILL SLOPES ARE 3:1 EXCEPT WHERE NOTED.
6. FILL AND BACKFILL MATERIAL SHALL BE COMPACTED TO 95% STD. PROCTOR DENSITY AT OPTIMUM MOISTURE $\pm 2\%$ UNLESS SPECIFIED OTHERWISE ON THE PLANS.
7. ALL GRADING OPERATIONS SHALL BE DONE IN SUCH A MANNER SO AS TO PROVIDE POSITIVE DRAINAGE AT ALL TIMES.
8. ANY AREA THAT IS DISTURBED OUTSIDE THE CONSTRUCTION LIMITS DURING THE LIFE OF THIS PROJECT SHALL BE REPAIRED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.

1.	CONTRACTOR SHALL VERIFY LOCATION, INVERT ELEVATIONS, AND SIZES OF ALL UTILITY MAINS AND LINES PRIOR TO INSTALLATION OF UTILITY MAINS (1-800-282-7411)	HDPE SDR 9 ASTM D3035
2.	ALL WATER AND SANITARY SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH LOCAL STANDARD SPECIFICATIONS FOR WATER AND SANITARY SEWER.	8. WATER MAINS SHALL BE DISINFECTED AND TESTED, BY THE CONTRACTOR, IN ACCORDANCE WITH AWWA STANDARDS, GEORGIA EPD STANDARDS, AND LOCAL STANDARDS.
3.	THE CONTRACTOR SHALL NOTIFY THE PROPER AUTHORITY 48 HRS. PRIOR TO MAKING CONNECTIONS TO EXISTING UTILITIES.	9. THE CONTRACTOR SHALL MEET ALL APPLICABLE FEDERAL, STATE, AND LOCAL CODES, LAWS, REGULATIONS AND REQUIREMENTS.
4.	UTILITY LINES MATERIALS SHALL BE IN ACCORDANCE WITH THE FOLLOWING:	10. PROVIDE DUCTILE IRON SEWER PIPE WHERE PIPE CROSSES STORM PIPE AND WHERE SEWER PIPE HAS LESS THAN 3 FT. COVER.
5.	SANITARY SEWER: PVC - ASTM 3034, SDR35 DUCTILE IRON - CLASS 350 AWWA C151	11. CONTRACTOR SHALL PROVIDE DEWATERING AS REQUIRED FOR INSTALLATION OF ALL UTILITIES
6.	WATER MAINS SDR-21 WITH THE APPROVAL FROM CITIES UTILITY DEPT. DUCTILE IRON PIPE - CLASS 350 AWWA C151	12. SEWERS MUST BE LOW-PRESSURE TESTED PER ASTM F 1417 OR HIGH-PRESSURE TESTED PER AWWA C 600, C605 OR OTHER INDUSTRY STANDARD.
7.	WATER SERVICE LINES (2" AND SMALLER) SCHEDULE 40 PVC	13. MANHOLES MUST BE VACUUM-TESTED PER ASTM C 1244 OR HYDRAULICALLY TESTED WITH LEAKS LIMITED TO 1/4 - INCH OVER 24 HOURS.
		14. ALL SEWERS MADE OF NON-METALLIC PIPE MUST INCLUDE TRACER WIRE AND LOCATOR TAPE AS SHOWN IN DETAILS

Storm Sewer Tabulation

Page 1

Station	Len	Dmg Area	Rnoff	Area x C	Tc	Rain	Total	Cap	Vel	Pipe	Invert Elev	HGL Elev	Grnd / Rim Elev	Line ID							
Line	To Line	Incr	Total	coeff	Incr	Total	Inlet	Syst		Size	Slope	Dn	Up	Dn	Up						
		(ft)	(ac)	(ac)	(C)		(min)	(min)		(in/hr)	(cfs)	(cfs)	(ft/s)	(in)	(%)	(ft)	(ft)	(ft)	(ft)		
1	End	131.498	0.00	0.00	0.00	0.00	0.0	0.0	0.0	53.76	100.7	8.94	36	2.28	408.00	411.00	410.38	413.38	411.83	414.83	ST-A1
Project File: STORM CALCS-C.stm												Number of lines: 1				Run Date: 7/24/2024					
NOTES: Intensity = 63.52 / (inlet time + 12.90) ^ 0.70; Return period =Yrs. 25 ; c = cir e = ellip b = box																					

Storm Sewers v2024.00

Pipe outlet headwall / Detention pond outlet	25 year post-developed flow velocity at outlet headwall (fps)	25 year post-developed flow (cfs)	Non-erosive velocity from Storm Water Design Manual	Energy Dissipation Measures proposed	W1 (ft)	W2 (ft)	La (ft)	Quantity (SY)	Average Stone Diameter (d50) in.
ST-A1	8.94	53.76	5.00	St	9	13	10	16	6
ST-B1	11.34	1980.00	5.00	St	96	144	120	520	12

Erosion & Sediment Control Calculations									
Sediment Control Calculations									
Sediment Storage Basin Phase 1									
Number	BMP	Disturbed Area (Ac.)	Length (ft)	Width (ft)	Depth (ft)	Factor (cy/ac)	Required Volume (cubic yd)	Provided Volume (cubic yd)	Adequate Protection?
1	Sd4-C	1.33	60	30	4	67	89.11	266.67	YES
2	Sd4-C	2.20	60	25	4	67	147.40	222.22	YES
3	Sd1-NS	6.16	na	na	na	67	412.72	1404.00	YES
Totals		9.69					649.23	1892.89	Yes

0504D-Erosion & Sediment Control Calculations Pete's Way Extension	
Silt Fence Calculations	
Total Area	362.53
Disturbed Area	6.16
Sediment Storage Required	V req = 67 CY x 6.16 = 412.72 CY
Sediment Storage Available	Length (L) of silt fence provided = 8386 ft
	Using the assumption that silt fence provides sediment storage for 1/4 acre per 100 ft, the available volume per foot of silt fence would equal 0.1675 CY/ft, (i.e. 1/4 acre x 67 CY / 100 ft = 0.1675 CY/ft)
	Vavail = L x 0.1675 CY/ft
	Vavail = 8386 ft x 0.1675 CY/ft
	Vavail = 1404 CY
	Vavail > Vreq

EROSION, SEDIMENTATION & POLLUTION CONTROL PLAN CHECKLIST		
INFRASTRUCTURE CONSTRUCTION PROJECTS		
SWCD:		
Project Name: PETE'S WAY EXTENSION		Address: PETE'S WAY, WARNER ROBINS, GA.
Local Issuing Authority: HOUSTON COUNTY		Date on Plans: 7/16/24
Name & Email of person filling out checklist: CHAD BRYANT, P.E. (chad@bryantgic.com)		
Plan Page #	Included	TO BE SHOWN ON ES&PC PLAN
0.2	<input type="checkbox"/>	1 The applicable Erosion, Sedimentation and Pollution Control Plan Checklist established by the Commission as of January 1 of the year in which the land-disturbing activity was permitted. (The completed Checklist must be submitted with the ES&PC Plan or the Plan will not be reviewed)
ALL	<input type="checkbox"/>	2 Level I certification number issued by the Commission, signature and seal of the certified design professional. (Signature, seal, and Level I number must be on each sheet pertaining to ES&PC Plan or the Plan will not be reviewed)
ALL	<input type="checkbox"/>	3 The name and phone number of the 24-hour contact responsible for erosion, sedimentation and pollution controls.
5.4	<input type="checkbox"/>	4 Provide the name, address, email address, and phone number of primary permittee.
0.1 & 5.1	<input type="checkbox"/>	5 Note total and disturbed acreages of the project or phase under construction.
5.5	<input type="checkbox"/>	6 Provide the GPS locations of the beginning and end of the Infrastructure project. Give the Latitude and Longitude in decimal degrees.
ALL	<input type="checkbox"/>	7 Initial date of the Plan and the dates of any revisions made to the Plan including the entity who requested the revisions.
5.4	<input type="checkbox"/>	8 Descriptions of the nature of construction activity and existing site conditions.
5.5	<input type="checkbox"/>	9 Provide vicinity map showing site's relation to surrounding areas. Include designation of specific phase, if necessary.
5.5	<input type="checkbox"/>	10 Identify the project reviewing waters and describe all sensitive adjacent areas including streams, lakes, residential areas, wetlands, etc. that may be affected.
5.5	<input type="checkbox"/>	11 Design professional's certification statement and signature that the site was visited prior to development of the ES&PC Plan as stated on Part IV page 21 of the permit.
5.5	<input type="checkbox"/>	12 Design professional's certification statement and signature that the permittee's ES&PC Plan provides for an appropriate and comprehensive system of BMPs and sampling to meet permit requirements as stated on Part IV page 20 of the permit.
5.5	<input type="checkbox"/>	13 Design professional certification statement and signature that the permittee's ES&PC Plan provides for representative sampling as stated on Part IV D.6.c.(3) page 37 of the permit as applicable.
5.4	<input type="checkbox"/>	14 Clearly note the statement that "The design professional who prepared the ES&PC Plan is to inspect the installation of the initial sediment-basins requirements, perimeter control BMPs, and sediment basins within 7 days after installation." in accordance with Part IV A.5 page 26 of the permit.
5.4	<input type="checkbox"/>	15 Clearly note the statement that "Non-exempt activities shall not be conducted within the 25 or 50-foot undisturbed stream buffer as measured from the point of natural vegetation or within 25 feet of the coastal marshland buffer as measured from the Jurisdictional Determination Line without first acquiring the necessary variances and permits."
5.4	<input type="checkbox"/>	16 Provide a description of any buffer encroachments and indicate whether a buffer variance is required.
5.4	<input type="checkbox"/>	17 Clearly note the statement that "Amendments/revisions to the ES&PC Plan which have a significant effect on BMPs with a hydraulic component must be certified by the design professional."
5.4	<input type="checkbox"/>	18 Clearly note the statement that "Waste materials shall not be discharged to waters of the State, except as authorized by a Section 404 permit."
5.4	<input type="checkbox"/>	19 Clearly note statement that "The escape of sediment from the site shall be prevented by the installation of erosion and sediment control measures and practices prior to land disturbing activities."
5.4	<input type="checkbox"/>	20 Clearly note statement that "Erosion control measures will be maintained at all times. If full implementation of the approved Plan does not provide for effective erosion control, additional erosion and sediment control measures shall be implemented to control or treat the sediment source."
5.4	<input type="checkbox"/>	21 Clearly note the statement "Any disturbed area left exposed for a period greater than 14 days shall be stabilized with mulch or temporary seeding."
5.5	<input type="checkbox"/>	22 Any construction activity which discharges storm water into an Impaired Stream Segment or within 1 linear mile upstream of and within the same watershed as, any portion of a Bate Impaired Stream Segment must comply with Part III, C. of the permit. Include the completed Appendix I listing all the BMPs that will be used for those areas of the site which discharge to the Impaired Stream Segment.
N/A	<input type="checkbox"/>	23 If a TMDL implementation Plan for sediment has been finalized for the Impaired Stream Segment (identified in Item 22 above) to allow for months prior to submittal of NOI, the ES&PC Plan must address any site-specific conditions or requirements included in the TMDL Implementation Plan.
5.5	<input type="checkbox"/>	24 BMPs for concrete washout of trucks, concrete mixer chutes, hoppers and the rear of the vehicles. Washout of the drum at the construction site is prohibited.
5.5	<input type="checkbox"/>	25 Provide BMPs for the remediation of all petroleum spills and leaks.
5.4-5.5	<input type="checkbox"/>	26 Description of the measures that will be installed during the construction process to control pollutants in storm water that will occur after construction operations have been completed.
5.5	<input type="checkbox"/>	27 Description of practices to provide cover for building materials and building products on site.
5.5	<input type="checkbox"/>	28 Description of the practices that will be used to reduce the pollutants in storm water discharge.
5.5	<input type="checkbox"/>	29 Description of creation and/or timeline of the intended sequence of major activities which disturb soils for the major portions of the site (i.e., initial perimeter and sediment grading BMPs, clearing and grubbing activities, excavation activities, utility activities, temporary and final stabilization).
5.5	<input type="checkbox"/>	30 Provide complete requirements of Inspections and record keeping by the primary permittee.
5.5	<input type="checkbox"/>	31 Provide complete requirements of Sampling Frequency and Reporting of sampling results.
5.5	<input type="checkbox"/>	32 Provide complete details for Retention of Records as per Part IV.F. of the permit.
5.5	<input type="checkbox"/>	33 Description of analytical methods to be used to collect and analyze the samples from each location.
5.5	<input type="checkbox"/>	34 Define B rational for NTU values at all outfall sampling points where applicable.
5.5	<input type="checkbox"/>	35 Appellate all sampling locations, perennial and intermittent streams and other water bodies into which storm water is discharged also provide a summary chart of the justification and analysis for the representative sampling as applicable.
5.1-5.2	<input type="checkbox"/>	36 A description of appropriate controls and measures that will be implemented at the construction site including: (1) initial sediment storage requirements and perimeter control BMPs; (2) intermediate grading and drainage BMPs, and (3) final BMPs. For construction sites where there will be no mass grading and the initial perimeter control BMPs, intermediate grading and drainage BMPs, and final BMPs are the same, the Plan may combine all of the BMPs into a single phase.
ALL	<input type="checkbox"/>	37 Graphic scale and North arrow.
ALL	<input type="checkbox"/>	38 Existing and proposed contour lines with contour lines drawn at an interval in accordance with the following: Existing Contours USGS 1' x 1" 2000' Topographical Sheets Proposed Contours 1" 400' Centerline Profile
N/A	<input type="checkbox"/>	39 Use of alternative BMPs whose performance has been documented to be equivalent to or superior to conventional BMPs as certified by a Design Professional (unless disapproved by GAEPD or the Georgia Soil and Water Conservation Commission). Please refer to the Alternative BMP Guidance Document found at www.gawccw.org/georgia .
N/A	<input type="checkbox"/>	40 Use of alternative BMP for application to the Equivalent BMP List. Please refer to Appendix A-2 of the Manual for Erosion & Sediment Control in Georgia 2016 Edition.
1.1	<input type="checkbox"/>	41 Delineation of the applicable 25-foot or 50-foot undisturbed buffers adjacent to State waters and any additional buffers required by the Local Issuing Authority. Clearly note and delineate all areas of impact.
1.1	<input type="checkbox"/>	42 Delineation of on-site wetlands and all State waters located on and within 200 feet of the project site.
Hydri	<input type="checkbox"/>	43 Delineation and acreage of contributing drainage basins on the project site.
Hydri	<input type="checkbox"/>	44 Delineate on-site drainage and off-site watersheds using USGS 1' x 1" 2000' topographical sheets.
Hydri	<input type="checkbox"/>	45 An estimate of the runoff coefficient and peak discharge flow of the site prior to and after construction activities are completed.
0.2	<input type="checkbox"/>	46 Storm-drain pipe and weir velocities with appropriate outlet protection to accommodate discharges without erosion. Identify/Delineate all storm water discharge points.
1.1	<input type="checkbox"/>	47 Soil series for the project site and their delineation.
5.1-5.2	<input type="checkbox"/>	48 The limits of disturbance for each phase of construction.
0.2	<input type="checkbox"/>	49 Provide a minimum of 67 cubic yards of sediment storage per acre drained using a temporary sediment basin, retrofitted detention pond, and/or excavated inlet sediment traps for each common drainage location. Sediment storage volume must be in place prior to and during all land disturbance activities until final stabilization of the site has been achieved. A written justification explaining the design to use equivalent controls when a sediment basin is not obtainable must be included in the Plan for each common drainage location in which a sediment basin is not provided. A written justification as to why 67 cubic yards of storage is not obtainable must also be given. Worksheets from the Manual must be included for structural BMPs and all calculations used by the design professional to obtain the required sediment storage when using equivalent controls. When discharging from sediment basins and impoundments, permittees are required to utilize outlet structures that withdraw water from the surface, unless infeasible. If outlet structures that withdraw water from the surface are not feasible, a written justification explaining this decision must be included in the Plan.
5.1-5.2	<input type="checkbox"/>	50 Location of Best Management Practices that are consistent with and no less stringent than the Manual for Erosion and Sediment Control in Georgia. Use uniform coding symbols from the Manual, Chapter 6, with legend.
5.6	<input type="checkbox"/>	51 Provide detailed drawings for all structural practices. Specifications must, at a minimum, meet the guidelines set forth in the Manual for Erosion and Sediment Control in Georgia.
5.1-5.2	<input type="checkbox"/>	52 Provide vegetative plan, noting all temporary and permanent vegetative practices. Include species, planting dates and seeding, fertilizer, lime and mulching rates. Vegetative plan shall be site specific for appropriate time of year that seeding will take place and for the appropriate geographic region of Georgia.





* If using the checklist for a project that is less than 1 acre and not part of a common development, but within 200 ft of a perennial stream, the "checklist items would be N/A.

Effective January 1, 2024




P:\03 - INSTITUTIONAL AUTHORITY\0322 - JOINT DEVELOPEMENT AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002-MASTER.DWG(3/24/2025 4:56 PM)


OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



MATCH LINE



SOILS INFORMATION	
AvP -	Alluvial land, wet
FoA -	Faceville fine sandy loam, 0 to 2 percent slopes
FoB -	Faceville fine sandy loam, 2 to 5 percent slopes
GpC3 -	Greenville clay loam, 5 to 8 percent slopes, severely eroded
LcC -	Lucy sand, 5 to 8 percent slopes
LcM -	Local alluvial land
LqD -	Lakeland fine sand, 5 to 12 percent slopes
NgC2 -	Norfolk loamy fine sand, 5 to 8 percent slopes eroded
VOD2 -	Vaucluse-Hoffman complex, 8 to 12 percent slopes, eroded



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

EXISTING CONDITIONS FOR:

PETE'S WAY EXTENSION


CITY OF WARNER ROBINS

GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION


SHEET NO.

C-1.1





ROAD LINE TABLE		
LINE #	LENGTH	DIRECTION
L1	778.89	N0° 06' 31.60"W
L2	849.58	N17° 54' 21.38"E
L3	355.53	N52° 19' 00.14"E
L4	654.81	N7° 18' 02.82"E

ROAD CURVE TABLE				
CURVE #	ARC	RADIUS	DIRECTION	LENGTH
C1	235.81	750.00	N8° 53' 54.89"E	234.84
C2	450.44	750.00	N35° 06' 40.76"E	443.70
C3	589.26	750.00	N29° 48' 31.48"E	574.22



OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOORY DRIVE
FORT VALLEY
478-825-3826

PETE'S WAY
SCALE: 1" = 50' HORZ.
1" = 5' VERT.



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 fax: (478) 224-7072
111 Fernster Road, Suite A P.O. Box 1821
Ferry, Georgia 31609
www.bryantengllc.com

COUNTY:	HOUSTON	03/5
LL/DISTRICT:	DWG:	0322-002-MASTER
DATE:	7/16/24	
SCALE:	1" = 50'	
JOB NO.:	0322-002	


THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

PLAN AND PROFILE FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION


SHEET NO.
C-2.2

OWNER:
JOINT DEVELOPEMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826





ROAD LINE TABLE		
LINE #	LENGTH	DIRECTION
L1	778.89	N0° 06' 31.60"W
L2	849.58	N17° 54' 21.38"E
L3	355.53	N52° 19' 00.14"E
L4	654.81	N77° 18' 02.82"E


ROAD CURVE TABLE				
CURVE #	ARC	RADIUS	DIRECTION	LENGTH
C1	235.81	750.00	N8° 53' 54.89"E	234.84
C2	450.44	750.00	N35° 06' 40.76"E	443.70
C3	589.26	750.00	N29° 48' 31.48"E	574.22



PETE'S WAY
SCALE: 1" = 50' HORZ.
1" = 5' VERT.



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.




PLAN AND PROFILE FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-2.4


P:\03 - INSTITUTIONAL AUTHORITY\0322 - JOINT DEVELOPEMENT AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002-MASTER.DWG(3/24/2025 4:56 PM)

OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 fax: (478) 224-7072
111 Fernster Road, Suite A P.O. Box 1821
Ferry, Georgia 31609
www.bryantengllc.com



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002




THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

RIGHT-OF-WAY, STRIPING PLAN, & SIGNAGE PLAN FOR
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-2.5

OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT ENGINEERING
P.O. Box 1821
Forty, Georgia 31069
phone: (478) 224-7070 fax: (478) 224-7072
www.bryantengllc.com

COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.




RIGHT-OF-WAY, STRIPING PLAN & SIGNAGE PLAN FOR
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-2.6


P:\03 - INSTITUTIONAL AUTHORITY\0322 - JOINT DEVELOPMENT AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002-MASTER.DWG(3/24/2025 4:53 PM)

OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 fax: (478) 224-7072
111 Fernster Road, Suite A P.O. Box 1821
Ferry, Georgia 31609
www.bryantengllc.com



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

GRADING & DRAINAGE PLAN FOR:

PETE'S WAY EXTENSION


CITY OF WARNER ROBINS

GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.

C-3.1





OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826

ENGINEERING "NO-RISE" CERTIFICATION


This is to certify that I am a duly qualified engineer licensed to practice in the State of Georgia.

It is to further certify that the attached technical data supports the fact that proposed Pete's Way Extension will not impact the 100 year flood elevations, floodway elevations and floodway widths on Sandy Run Creek at published sections in the Flood Insurance Study for City of Warner Robins, Peach County, dated September 26, 2008 and will not impact the 100 year flood elevations, floodway elevations, and floodway widths at unpublished cross-sections in the vicinity of the proposed development.


	034595	11/8/24
DESIGN PROFESSIONAL	LICENSE #	DATE

													
CHAD R. BRYANT, P.E. GSWCC LEVEL II DESIGN PROFESSIONAL CERTIFICATION # 24356													
<h1 style="margin: 0;">BRYANT ENGINEERING</h1> <p style="font-size: small; margin-top: 5px;"> 111 Perimeter Road, Suite A • P.O. Box 1821 Perry, Georgia 31069 Phone: (478) 221-2200 Fax: (478) 221-7172 www.bryantengllc.com </p>													
<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <th style="padding: 2px;">COUNTY:</th> <td style="padding: 2px;"><i>Houston</i></td> </tr> <tr> <th style="padding: 2px;">LL/DISTRICT:</th> <td style="padding: 2px;"><i>63/5</i></td> </tr> <tr> <th style="padding: 2px;">DWG:</th> <td style="padding: 2px;"><i>0222-002-MASTER</i></td> </tr> <tr> <th style="padding: 2px;">DATE:</th> <td style="padding: 2px;"><i>7/16/24</i></td> </tr> <tr> <th style="padding: 2px;">SCALE:</th> <td style="padding: 2px;"><i>1"= 50'</i></td> </tr> <tr> <th style="padding: 2px;">JOB NO.:</th> <td style="padding: 2px;"><i>0222-002-</i></td> </tr> </table>	COUNTY:	<i>Houston</i>	LL/DISTRICT:	<i>63/5</i>	DWG:	<i>0222-002-MASTER</i>	DATE:	<i>7/16/24</i>	SCALE:	<i>1"= 50'</i>	JOB NO.:	<i>0222-002-</i>	<p style="font-size: x-small; margin-bottom: 10px;">THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY. NOTES AS TO RELEASE FOR CONSTRUCTION, THIS DRAWING MAY NOT BE REPRODUCED WITHOUT CORRECTED WRITTEN CONSENT.</p> <div style="text-align: right; padding-right: 10px;"> <p style="font-weight: bold; font-size: large; margin: 0;">GEORGIA</p> </div>
COUNTY:	<i>Houston</i>												
LL/DISTRICT:	<i>63/5</i>												
DWG:	<i>0222-002-MASTER</i>												
DATE:	<i>7/16/24</i>												
SCALE:	<i>1"= 50'</i>												
JOB NO.:	<i>0222-002-</i>												
<h2 style="margin: 0;">GRADING & DRAINAGE PLAN FOR:</h2> <h1 style="margin: 0; letter-spacing: 0.5em;">PETE'S WAY EXTENSION</h1> <h2 style="margin: 0;">CITY OF WARNER ROBINS</h2>													
SHEET NO. <h1 style="margin: 0;">C-3.2</h1>													


OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



STORM A
SCALE: 1" = 50' HORZ.
1" = 5' VERT.



STORM B
SCALE: 1" = 50' HORZ.
1" = 5' VERT.



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT

ENGINEERING

phone: (478) 224-7070 • fax: (478) 224-7072

111 Fernster Road, Suite A

Ford, Georgia 30069

www.bryantengllc.com

www.bryantengllc.com

COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

DRAINAGE PROFILES FOR:























PETE'S WAY EXTENSION

CITY OF WARNER ROBINS

GEORGIA


REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-3.3



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 fax: (478) 224-7072
111 Fernster Road, Suite A P.O. Box 1821
Ferry, Georgia 31609






COUNTY:	HOUSTON
LD/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1"= 50'
JOB NO.:	0322-002




THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.




















CROSS SECTIONS FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-3.4



[illegible]



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING

phone: (478) 224-7070 fax: (478) 224-7072
111 Fernster Road, Suite A P.O. Box 1821
Ferry, Georgia 31609

www.bryantengllc.com

COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1"= 50'
JOB NO.:	0322-002

THE DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.


CROSS SECTIONS FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS

GEORGIA


REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-3.8

P:\03 - INSTITUTIONAL AUTHORITY\0322 - JOINT DEVELOPEMENT AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002-MASTER.DWG(3/24/2025 4:51 PM)




OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 • fax: (478) 224-7072
111 Fernside Road, Suite A
Ferry, Georgia 31609
www.bryantengllc.com



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THIS DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.



UTILITY PLAN FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-4.1

P:\03 - INSTITUTIONAL AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002-MASTER.DWG (3/24/2025 4:54 PM)

OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826





THE EXISTING UTILITIES SHOWN ON THIS PLAN WERE OBTAINED FROM
VARIOUS UTILITY COMPANIES, VARIOUS GOVERNMENTAL AGENCIES, AND
ABOVE-GROUND OBSERVATION. THE SURVEYOR AND/OR ENGINEER MAKE
NO CLAIM TO THE COMPLETENESS OF THIS INFORMATION. THE SIZE,
LOCATION, OR ADDITIONAL UTILITIES MAY BE UNCOVERED UPON
EXCAVATION. PRIOR TO BEGINNING ANY EARTH DISTURBING ACTIVITIES,
THE UTILITY PROTECTION SERVICE FOR THIS AREA MUST BE NOTIFIED.



IF YOU DIG GEORGIA ...
CALL US FIRST
UTILITIES PROTECTION CENTER
STATE WIDE
1 800 282-7411
IT'S THE LAW




Know what's below.
Call before you dig.



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 • fax: (478) 224-7072
111 Fernmer Road, Suite A •
Ferry, Georgia 31609
www.bryantengllc.com



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002


THIS DRAWING IS THE PROPERTY OF BRYANT
ENGINEERING, LLC AND IS RELEASED AS
PRELIMINARY / REVIEW ONLY UNLESS NOTED
AS RELEASED FOR CONSTRUCTION. THE
DRAWING MAY NOT BE REPRODUCED WITHOUT
EXPRESSED WRITTEN CONSENT.

UTILITY PLAN FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-4.2

P:\03 - INSTITUTIONAL AUTHORITY\0322 - JOINT DEVELOPEMENT AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002 MASTER.DWG(3/24/2025 4:53 PM)



REVISIONS

NO.	DATE	DESCRIPTION

SHEET NO.

C-4.3

SANITARY SEWER PROFILES FOR:

PETE'S WAY EXTENSION

CITY OF WARNER ROBINS

COUNTY: HOUSTON

DWG: 0322-002-MASTER

DATE: 7/16/24

SCALE: 1" = 50'

JOB NO.: 0322-002

REGISTERED

ENGINEER

CHAD R. BRYANT, P.E.

033595

033595

033595

CHAD R. BRYANT, P.E.

GSWCC LEVEL II

DESIGN PROFESSIONAL

CERTIFICATION # 24596

BRYANT

ENGINEERING

111 Fernside Road, Suite A

Ft. Valley, Georgia 31609






Phone: (478) 224-7070

Fax: (478) 224-7072

P.O. Box 1821

Ft. Valley, Georgia 31609

www.bryantengllc.com



OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826

REGISTERED
No. 033595
PEACH COUNTY
ENGINEER
CHAD R. BRYANT, P.E.

CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING

phone: (478) 224-7070 • fax: (478) 224-7072
111 Fernster Road, Suite A
Ferry, Georgia 31609

www.bryantengllc.com

COUNTY: HOUSTON
LD/DISTRICT: 03/5
DWG: 0322-002-MASTER
DATE: 7/16/24
SCALE: 1" = 50'
JOB NO.: 0322-002



THE DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

SANITARY SEWER PROFILES FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS
NO. DATE DESCRIPTION
SHEET NO.
C-4.4

0504D-Erosion & Sediment Control Calculations Pete's Way Extension	
Silt Fence Calculations	
Total Area	362.53
Disturbed Area	6.16
Sediment Storage Required	V req= 67 CY X 6.16 = 412.72 CY
Sediment Storage Available	Length (L) of silt fence provided = 8386 ft Using the assumption that silt fence provides sediment storage for 1/4 acre per 100 ft, the available volume per foot of silt fence would equal 0.1675 CY/ft. (i.e. 1/4 acre x 67 CY / 100 ft = 0.1675 CY/ft)
	Vavail = L x 0.1675 CY/ft Vavail = 8386 ft x 0.1675 CY/ft Vavail = 1404 CY
	Vavail > Vreq

Erosion & Sediment Control Calculations									
Sediment Control Calculations									
Sediment Storage Basin Phase 1									
Number	BMP	Disturbed Area (Ac.)	Length (ft)	Width (ft)	Depth (ft)	Factor (cy/ac)	Required Volume (cubic yd)	Provided Volume (cubic yd)	Adequate Protection?
1	Sd4-C	1.33	60	30	4	67	89.11	266.67	YES
2	Sd4-C	2.20	60	25	4	67	147.40	222.22	YES
3	Sd1-NS	6.16	na	na	na	67	412.72	1404.00	YES
Totals		9.69					649.23	1892.89	Yes



PHASE 1 SEQUENCE NOTES:


1. INSTALL STABILIZED CONSTRUCTION EXIT. THIS WILL BE THE FIRST CONSTRUCTION WORK ON THE PROJECT;
2. INSTALL CONSTRUCTION FENCE ALONG ANY STREAM BUFFERS, WETLANDS AND OTHER ENVIRONMENTALLY SENSITIVE AREAS AS SHOWN ON PHASE 1 PLAN TO ESTABLISH THE NON-DISTURB STREAM BUFFERS AND LIMITS OF CONSTRUCTION;
3. INSTALL SILT FENCE AS SHOWN ON THE PHASE 1 PLAN;
4. CLEAR AND GRUB THE AREA REQUIRED TO CONSTRUCT THE SEDIMENT STORAGE FACILITY;
5. CONSTRUCT SEDIMENT STORAGE FACILITY, OUTLET STRUCTURE, AND DISCHARGE SWALE. INSTALL SURFACE SKIMMER DEWATERING DEVICE AS REQUIRED;
6. APPLY SEEDING & MATTING TO DISTURBED AREAS;
7. CLEAR AND GRUB THE AREA REQUIRED TO CONSTRUCT THE ACCESS ROAD, PARKING/BUILDING AREA, AND SWALES;
8. CONSTRUCT ACCESS ROAD, PARKING/BUILDING AREAS, AND SALES. APPLY SEEDING, MATTING, AND INSTALL ROCK CHECK DAMS IN SWALES;
9. INSTALL STORM PIPE AND INLETS WITH INLET PROTECTION AS SHOWN ON PHASE 1 PLAN TO DIRECT STORMWATER TO POND;
10. STABILIZE ACCESS ROADS AND PAVEMENT AREAS WITH STONE AS SOON AS PRACTICAL;
11. APPLY SEED, STRAW/MATting TO ALL REMAINING DISTURBED AREAS;
12. ONCE GRADING OF THE STORMWATER CONVEYANCE SWALES ARE COMPLETED, REMOVE SILT FENCE FROM CONCENTRATED FLOW PATHS.

PHASE 2 SEQUENCE NOTES:


1. INSTALL SILT FENCE AS SHOWN ON THE PHASE 2 PLAN;
2. CLEAR AND GRUB THE AREA REQUIRED TO CONSTRUCT THE SEDIMENT STORAGE FACILITY AND DISCHARGE SWALES;
3. CONSTRUCT SEDIMENT STORAGE FACILITY, OUTLET STRUCTURES, AND DISCHARGE SWALES AND INSTALL ANY SURFACE SKIMMER DEWATERING DEVICE AS REQUIRED.
4. APPLY SEEDING & MATTING TO DISTURBED AREAS;
5. CLEAR AND GRUB THE AREA REQUIRED TO PERFORM GRADING OPERATIONS;
6. GRADE THE SITE AS REQUIRED. APPLY SEEDING, MATTING, AND INSTALL ROCK CHECK DAMS IN THE SWALES AS REQUIRED;
7. INSTALL STORM PIPE AND AREA DRAINS WITH INLET PROJECTION AS SHOWN ON PHASE 2 PLAN TO DIRECT STORMWATER TO POND;
8. STABILIZE SITE WITH STONE OR GAB AS SOON AS PRACTICAL;
9. APPLY SEED, STRAW/MATting TO ALL REMAINING DISTURBED AREAS;
10. ONCE GRADING OF THE MAIN DRAINAGE WAYS ARE COMPLETED, REMOVE SILT FENCE FROM CONCENTRATED FLOW PATH.

PHASE 3 SEQUENCE NOTES:

1. INSTALL/ADJUST SILT FENCE AS SHOWN ON THE PHASE 3 PLAN;
2. APPLY SEEDING & MATTING TO DISTURBED AREAS AS SHOWN;
3. APPLY SEED, STRAW/MATting TO ALL REMAINING DISTURBED AREAS;
4. REMOVE EROSION AND SEDIMENT CONTROL MEASURES ONLY AFTER UPSTREAM AREA IS FULLY STABILIZED;
5. AFTER THE CONSTRUCTION SITE HAS BEEN FULLY STABILIZED, REMOVE ALL TEMPORARY BASIN STRUCTURES AND SEDIMENT IN SUCH A MANNER AS TO NOT ALLOW SEDIMENT TO BE DISCHARGED FROM THE BASINS. ALL REMOVED CONSTRUCTION PHASE SEDIMENT SHALL BE PLACED BACK ON THE PROJECT SITE AS DIRECTED BY THE PROJECT ENGINEER AND PERMANENTLY STABILIZED.
6. UPON FINAL STABILIZATION OF ALL DISTURBED AREAS, COMPLETE & SUBMIT THE NOTICE OF TERMINATION (NOT) TO EPD.




OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING
phone: (478) 224-7070 • fax: (478) 224-7072
111 Fernmeier Road, Suite A
Perry, Georgia 31069



COUNTY:	HOUSTON
LL/DISTRICT:	03/5
DWG:	0222-002-MASTER
DATE:	7/10/24
SCALE:	1" = 50'
JOB NO.:	0222-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC, AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.



EROSION CONTROL PLAN FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-5.1

P:\03 - INSTITUTIONAL AUTHORITY\0322-002 ROAD EXTENSION PROJECT\04 - DESIGN CAD\01 - DWG\0322-002-MASTER.DWG(3/24/2025 4:52 PM)

OWNER:
JOINT DEVELOPMENT AUTHORITY OF
PEACH COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826



CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING

phone: (478) 224-7070 • fax: (478) 224-7072
111 Fernmeier Road, Suite A • P.O. Box 1821
Ferry, Georgia 31609

www.bryantengllc.com

COUNTY:	HOUSTON
LL/DISTRICT:	03/25
DWG:	0322-002-MASTER
DATE:	7/16/24
SCALE:	1" = 50'
JOB NO.:	0322-002

THIS DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE DRAWING MAY NOT BE REPRODUCED WITHOUT EXPRESSED WRITTEN CONSENT.

EROSION CONTROL PLAN FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS
GEORGIA

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-5.2

I. EROSION CONTROL MEASURES

Erosion and Sedimentation Control Measures

1. Shall be installed before clearing and grubbing has commenced, if practical.
2. Shall conform to the standards set forth in the "Manual for Erosion and Sediment Control In Georgia".
3. Shall be maintained at all times, i.e. cleaned out, replaced if necessary.
4. The erosion and sediment control measures specified in these documents are minimum requirements. Additional measures may be needed to control sediment as required by law. Changes and reinforcements are required when failure of the erosion control measure persists.
5. All amendments or revisions to the ES&PC plan that affect BMP's with a hydraulic component must be certified by the Engineer. Revisions or amendments should be submitted to the Local Issuing Authority for review.

II. TEMPORARY EROSION CONTROL MEASURES

1. General

- a. Scope
 - i. Installation of temporary erosion control measures, such as, but not limited to, grassing, mulching, retrofitting of weir structures, silt gates, construction exits, check dams, inlet sediment traps, and sediment basins.
 - ii. Maintenance of soil erosion and sediment control devices during construction.
 - iii. Removal of temporary soil erosion and sediment control devices after disturbed areas have been permanently stabilized.
- b. Quality Assurance
 - i. After the specified erosion control devices called for in these documents have been installed, the Operator shall ensure that all reasonable measures have been taken to prevent siltation of nearby properties or water courses. If the Operator suspects that additional measures are needed, he shall immediately notify the Engineer. If rain is predicted before the Engineer is able to visit the site, the Operator shall install additional erosion control measures to minimize erosion and sedimentation.
 - ii. The erosion and sediment control shall conform with the Georgia Erosion and Sedimentation Act of 1975, as amended, and the "Manual for Erosion and Sediment Control in Georgia".

2. Products

- Ds1**
- Ds2**
- Cd**
- Co**
- Rt**
- Sd1**
- Sd2**
- Sd3**
- a. Mulching (Ds1) shall be a grain straw, hay, or wood waste. Any other material must be approved by the Engineer before use.
 - b. Temporary Seeding (Ds2) shall be an annual ryegrass or pearl millet. Other grassing may be substituted if proved effective by the Operator. Any substitutions must be approved by the Engineer before use.
 - c. Check Dam (Cd) shall be constructed with a 2-10 inch graded stone underlaid with a geotextile that complies with AASHTO M288-96 Section 7.3, Separation Requirements, Table 3.
 - d. Construction Exit (Co) shall be constructed of 1.5-3.5 inch stone and in accordance with the National Stone Association R-2 with an approved geotextile underneath. The geotextile shall comply with AASHTO M288-96 Section 7.3, Separation Requirements, Table 3.
 - e. Retrofitting (Rt) shall be constructed of a half round pipe with a stone filter. The pipe and stone shall conform to the specified dimensions in these documents.
 - f. Sediment Barrier (Sd1) shall be silt fence that conforms to the current Georgia Department of Transportation specifications. The approved fabrics are listed in the GDOT Qualified Products List #36 (QPL-36).
 - g. Inlet Sediment Trap (Sd2) is a protective device formed around a storm drain drop inlet to trap sediment. Inlet sediment traps shall be constructed of Type C - Silt Fence with nominal 2 x 4 boards bracing the corners to eliminate collapse.
 - h. Temporary Sediment Basin (Sd3) shall be a constructed on site and consist of a drainage structure to allow storm water to flow from site at a slower rate than normal. The sediment basin shall be constructed to the dimensions and specifications provided in these documents.

3. Execution

- a. General
 - i. All erosion and sediment control items shall be installed at the earliest practical time to minimize erosion on the project.
 - ii. Construct temporary erosion control measures as shown on the plans, and as required by site conditions, regulatory agency or Engineer. All permanent erosion control work shall be incorporated into the project at the earliest practical time. Temporary erosion control measures shall be coordinated with permanent erosion control measures and all work on the project to ensure economical, effective, and continuous erosion control throughout the construction and post construction period and to minimize escape of sediment onto adjacent properties or siltation of rivers, streams, lakes, or reservoirs.
 - iii. If active construction ceases for more than 14 days, all disturbed areas shall be seeded and mulched using temporary seed type and planting rates specified in these documents.
 - iv. Grading activity shall be controlled to prevent any damage to public or private property. Fines may be placed on the project by the local regulatory agencies due to soil erosion from the project site. Clearing shall be only in the areas required to install the soil erosion control devices.
 - v. A request shall be made for an inspection by the local agency having jurisdiction.
 - vi. All erosion control devices shall be inspected after each rainfall. Any required repairs shall be made immediately. Sediment deposits shall be removed when deposits reach approximately one-half of the capacity of the erosion control devices.
- b. Mulching
 - i. Shall be performed within 14 days of disturbance, or as required by the erosion control inspector.
 - ii. Shall be uniform and have 90% coverage.
 - iii. Hand spreading or blower spreading is acceptable as long as acceptable coverage is accomplished.
 - iv. Straw/Hay shall be installed at a depth of 2-4 inches.
 - v. Wood waste shall be applied a depth of 2-3 inches.
- c. Temporary Seeding
 - i. Shall be performed within 14 days of disturbance, or as required by the erosion control inspector.
 - ii. Shall be uniform and have 90% coverage.
 - iii. Hand spreading, mechanical spreading, and hydroseeding are all acceptable application methods.
 - iv. Lime
 1. Shall be applied at rates recommended by the University of Georgia Extension Service, or;
 2. Two tons per acre.

Temporary seed shall be in accordance with the following schedule: (All rates are PLS.)

TEMPORARY SEEDING	LBS/ ACRE		DEPTH OF COVER	DATE OF PLANTING
	ALONE	MIXTURES		
ANNUAL RYEGRASS	40	N/A	1/4" - 1/2"	8/15 - 3/31
PEARL MILLET	50	N/A	1/4" - 1/2"	4/1 - 8/31
BROWN TOP MILLET	40	10	1/4" - 1/2"	4/1 - 7/15

- Cd**
- Co**
- Rt**
- Sd1**
- Sd2**
- Sd3**
- a. Check Dam
 - i. Shall be installed in ditches, swales, or area of concentrated flow. Although, check dams shall never be installed in live streams.
 - ii. Used as ditch protection while grass linings are established.
 - iii. Used to control localized erosion in other areas.
 - iv. If area is to be mowed, the check dam shall be removed after final stabilization. If the area is not to be mowed, the check may be left in place.
 - b. Construction Exit
 - i. Shall be installed at the project exit.
 - ii. Intended to clean vehicle tires before entering roadway to eliminate off-tracking. Washing of tires will be required if the construction exit is not removing mud from tires effectively.
 - iii. Shall be a minimum of 50 feet long, 20 feet wide, and 6 inches thick. Geotextile liner shall be installed underneath stone.
 - c. Retrofitting
 - i. Shall be installed in front of detention pond outlet structures.
 - ii. Shall serve as a temporary sediment filter.
 - iii. Shall be kept free of trash and sediment deposits.
 - d. Sediment Barrier
 - i. Silt Fence Shall be installed around perimeter of project to control sheet flow, and in other areas to slow down storm water runoff.
 - ii. Silt fence shall be installed in a trench 6 inches deep and backfilled.
 - iii. Type "C" silt fence shall be tight with steel posts spaced at a maximum of 4 feet apart with woven wire fence backing that shall be tight and connected to steel posts. Type "NS" silt fence shall be tight with wood posts spaced at a max. of 6'-3" with no wire backing.
 - e. Inlet Sediment Trap
 - i. Shall be installed around the perimeter of storm drain inlet structures.
 - ii. Shall be constructed of Type "S" silt fence, including steel posts, woven wire fence backing, and filter fabric.
 - iii. Shall be tight around structure with post spacing not to exceed 3 foot spacing.
 - iv. Shall have at least two boards bracing the corners to minimize chance of failure.
 - v. Shall be trenched in or backfilled with stone.
 - f. Temporary Sediment Basin
 - i. Shall be constructed on site by excavation of a hole to accommodate storm water during construction.
 - ii. Shall be constructed during initial grading of the project to ensure the storm water is properly treated before discharged.
 - iii. May be used in conjunction with the permanent detention pond. If so, undercutting of the permanent detention pond may be required.
 - iv. Shall be constructed in strict accordance with these documents to be effective.
 - g. Removal of Temporary Erosion Control Devices
 - i. All temporary erosion and sedimentation control devices shall be removed when final stabilization has been achieved. Approval shall be given by the local issuing authority or the Engineer.
 - ii. All sediment deposits remaining shall be removed and disposed of. Disturbed area shall be dressed and graded to proposed grade, and finally permanently grassed.

III. PERMANENT EROSION & SEDIMENTATION CONTROL MEASURES

1. General

- a. Work Included
 - i. Provide all material, labor, equipment, tools, supervision, coordination, and other items necessary to provide permanent erosion and sedimentation control on the project.
 - ii. Includes seedbed preparation, top soiling, liming, fertilizing, seeding, and mulching of all areas inside and outside the limits of this project that were disturbed by the Operator.
 - iii. Includes installation of structural erosion and sedimentation control devices, which include but not limited to, installing rip rap stone in channels or at outlet ends of storm drain pipes.
- b. Lime
 - i. Agricultural lime is required unless soil tests indicate otherwise.
 - ii. Shall be free flowing with no lumps.
- c. Fertilizer
 - i. Fertilizer is required unless soil tests indicate otherwise.
- d. Mulch
 - i. Grain straw or hay free of weeds shall be used as mulch.
- e. Storm Drain Outlet Protection
 - i. Shall be DOT Type 3 rip rap stone.
 - ii. Shall be underlaid with an approved geotextile.
- f. Channel Stabilization
 - i. Rip Rap (Ch-Rp) shall conform to same specifications as Storm Drain Outlet Protection (above).
 - ii. Concrete Lining (Ch-C)
 1. Shall be 3000 psi concrete.
 2. One cubic foot of #57 stone is required at each weep hole.

3. Execution

- a. Seeding
 - i. Seedbed preparation shall be done on all grassed areas. This shall consist of harrowing and/or mixing to a minimum depth of 4 inches
 - ii. Rocks and debris left on the surface after tillage larger than one inch shall be removed.
 - iii. Soil shall not be muddy or in an undesirable condition for grassing.
 - iv. Within 24 hours of seedbed preparation, the seed shall be applied. Hydroseeding or handspreading is acceptable.
 - v. Seed shall be covered with the use of a spike tooth harrow.

Permanent seeding shall be in accordance with the following schedule:

(All rates are PLS.)

PERMANENT SEEDING	LBS/ ACRE		DEPTH OF COVER	DATE OF PLANTING
	ALONE OR W/TEMP.	W/OTHER PERENNIAL		
COMMON BERMUDA (HULLED)	10	6	1/4" - 1/2"	2/15 - 6/30
COMMON BERMUDA (UNHULLED)	10	6	1/4" - 1/2"	11/1 - 1/31
PENSACOLA BAHIA	60	30	1/4" - 1/2"	1/1 - 12/31
WEEPING LOVEGRASS	4	2	1/4" - 1/2"	2/1 - 6/15

- vi. Lime
 1. Shall be applied at rates recommended by the University of Georgia Extension Service, or;
 2. Two tons per acre.
- vii. Seeded areas shall be protected from traffic including but not limited to foot, vehicular, equipment traffic.
- b. Mulch
 - i. Shall be applied by hand or mechanical means.
 - ii. Shall be evenly distributed on grassed areas.
 - iii. Shall be applied at a rate of 2.5 tons per acre to achieve at least 75% coverage.
- c. Storm Drain Outlet Protection
 - i. Shall be installed at a depth of 18" minimum.
 - ii. All geotextile joints shall be overlapped at least one foot with the top layer on the upstream side.
 - iii. Shall be installed in accordance with these documents.
- d. Channel Stabilization
 - i. Shall have a minimum thickness of 4 inches.
 - ii. Shall have a toewall on the upstream and downstream ends. Toewall shall be one foot deep and one foot long for the entire width of the channel.
 - iii. Weep holes shall be installed 10 feet apart along the length of the lining.
 - iv. Shall be installed in accordance with these documents.
- e. Maintenance
 - i. All erosion and sedimentation control devices shall be maintained at all times.
 - ii. If full implementation of the approved plan does not provide adequate erosion and sedimentation control, additional devices shall be installed to treat the sediment source.
 - iii. All erosion control measures designed to collect sediment when the control device is have full or before.
 - iv. Upon completion of the project, all accumulated sediment shall be removed and proposed grade shall be achieved.

4. Fertilizer

Commercial grade, free flowing, uniform in composition and bearing the manufacturer's guaranteed statement of analysis. Analysis of fertilizer and application rates shall be as recommended by the University of Georgia County Extension Service through soil testing procedures, and in accordance with this schedule:

- 1/ Apply in spring following seeding.
- 2/ Apply in split applications when high rates are used
- 3/ Apply to grass species only when high rates are used
- 4/ Apply when plants grow to height of 2 to 4 inches

TYPE OF SPECIES	FERTILIZER REQUIREMENTS			N TOP DRESSING RATE
	LBS/ ACRE	ANALYSIS OR EQUIVALENT N-P-K	RATE	
1. COOL SEASON GRASSES	FIRST	6-12-12	1500 lbs/ac	50-100 lbs/ac 1/2/
2. COOL SEASON GRASSES AND LEGUMES	FIRST	6-12-12	1500 lbs/ac 1000 lbs/ac 400 lbs/ac	0-50 lbs/ac 3/
3. WARM SEASON GRASSES	FIRST	6-12-12	1500 lbs/ac	50-100 lbs/ac 2/4/
4. WARM SEASON GRASSES & LEGUMES	FIRST	6-12-12	1500 lbs/ac	50 lbs/ac 4/

WETLAND CERTIFICATION

THE DESIGN PROFESSIONAL, WHOSE SEAL APPEARS HEREON, CERTIFIES THE FOLLOWING:

- 1) THE NATIONAL WETLANDS INVENTORY MAPS HAVE BEEN CONSULTED, AN ONSITE JURISDICTIONAL WATERS DELINEATION/DETERMINATION HAS BEEN PERFORMED; AND,
- 2) THE APPROPRIATE PLAN SHEET DOES INDICATE AREAS OF UNITED STATES ARMY CORPS OF ENGINEERS JURISDICTIONAL WETLANDS AS SHOWN ON THE MAPS; AND,
- 3) IF WETLAND ARE INDICATED, THE LAND OWNER OR DEVELOPER HAS BEEN ADVISED THAT LAND DISTURBANCE OF PROTECTED WETLANDS SHALL NOT OCCUR UNLESS THE APPROPRIATE FEDERAL WETLANDS ALTERATION ("SECTION 404") PERMIT HAS BEEN OBTAINED.
- 4) ANY AMOUNT OF DISTURBANCE WILL REQUIRE PRE CONSTRUCTION COORDINATION WITH THE ARMY CORPS OF ENGINEERS.
- 5) TOTAL DISTURBANCE OF WETLANDS REQUIRED FOR DEVELOPMENT IS CALCULATED FROM ALL STAGES OF DEVELOPMENT.

④ 24 HR. LOCAL EMERGENCY CONTACT

B.J. WALKER
(478) 825-3826
EMAIL: bj-walker@peachcounty.net

⑤ OWNER/PRIMARY PERMITTEE

JOINT DEVELOPMENT AUTHORITY OF PEACH
COUNTY & CITY OF WARNER ROBINS
425 JAMES E. KHOURY DRIVE
FORT VALLEY
478-825-3826
EMAIL: bj-walker@peachcounty.net

⑥ TOTAL AND DISTURBED ACERAGE

TOTAL SITE AREA = 362.53 AC.
TOTAL DISTURBED AREA = 9.69 AC.

⑦ GPS LOCATION OF CONSTRUCTION EXIT

LAT.: N32.601652° LONG.: W83.727704°

⑨ DESCRIPTION OF CONSTRUCTION ACTIVITIES

THIS PROPOSED PROJECT IS AN EXTENSION TO THE EXISTING 30' WIDE ROAD WITH 120' R/W THAT WILL CONNECT CRESTVIEW CHURCH ROAD TO WATSON BLVD IN WARNER ROBINS, GA. THE TOTAL SITE CONTAINS 362.53 ACRES BUT THE PROJECT WILL ONLY DISTURB 9.69 ACRES. THE COMPLETED ROAD WILL BE ± 3720 L.F. LONG AND WILL BE 30' WIDE. THE PROPOSED ROAD WILL CROSS SANDY RUN CREEK AND A BOX CULVERT HAS BEEN DESIGNED TO ALLOW THE FLOW UNDER THE ROAD. THE PROJECT WILL HAVE PROPOSED 12" WATER LINE, ±3500 L.F., AND 12" SEWER LINE, ± 3443.00 L.F., RUNNING INSIDE THE R/W. DITCHES ON BOTH SIDE OF THE ROAD WILL CONVEY WATER INTO SANDY RUN CREEK WHERE AN EXISTING DETENTION POND WILL PROVIDE THE REQUIRED WATER QUALITY, CHANNEL PROTECTION, AND DETENTION FOR THE AREA.

⑭ THE DESIGN PROFESSIONAL WHO PREPARED THE ES&PC PLAN IS TO INSPECT THE INSTALLATION OF THE INITIAL SEDIMENT STORAGE REQUIREMENTS AND PERIMETER CONTROL BMP'S WITHIN 7 DAYS AFTER INSTALLATION

⑮ NON-EXEMPT ACTIVITIES SHALL NOT BE CONDUCTED WITHIN THE 25 OR 50-FOOT UNDISTURBED STREAM BUFFERS AS MEASURED FROM THE POINT OR WRESTED VEGETATION OR WITHIN 25-FEET OF THE COASTAL MARSHLAND BUFFER AS MEASURED FROM THE JURISDICTIONAL DETERMINATION LINE WITHOUT FIRST ACQUIRING THE NECESSARY VARIANCES AND PERMITS.

⑮ DESCRIPTION OF STREAM BUFFER ENCROACHMENT

NO STREAM BUFFER ENCROACHMENT IS PROPOSED AND THEREFORE, NO VARIANCE IS REQUIRED.

⑰ AMENDMENTS/REVISIONS TO THE ES&PC PLAN WHICH HAVE A SIGNIFICANT EFFECT ON BMP'S WITH A HYDRAULIC COMPONENT MUST BE CERTIFIED BY THE DESIGN PROFESSIONAL.

⑱ WASTE MATERIALS SHALL NOT BE DISCHARGED TO WATERS OF THE STATE, EXCEPT AS AUTHORIZED BY A SECTION 404 PERMIT.

⑲ THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO LAND DISTURBANCE ACTIVITIES.

⑳ EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE.

㉑ ANY DISTURBED AREA LEFT EXPOSED FOR A PERIOD GREATER THAN 14 DAYS SHALL BE STABILIZED WITH MULCH OR TEMPORARY SEEDING.

BEST MANAGEMENT PRACTICES (BMP's)

GEORGIA
UNIFORM CODING SYSTEM
GEORGIA SOIL AND WATER CONSERVATION COMMISSION
FOR SOIL EROSION AND SEDIMENT CONTROL PRACTICES

STRUCTURAL PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Cd	CHECK DAM			A small temporary barrier or dam constructed across a weir, drainage ditch or area of concentrated flow.
Ch	CHANNEL STABILIZATION			Improving, constructing or stabilizing an open channel, existing stream, or ditch.
Co	CONSTRUCTION EXIT			A crushed stone pad located at the construction exit used to provide a place for removing mud from tires thereby protecting public streets.
Cr	CONSTRUCTION ROAD STABILIZATION			A toweway constructed as part of a construction plan including access roads, subdivision roads, parking areas and other on-site while transportation routes.
Dc	STEAM EROSION CHANNEL			A temporary channel constructed to convey flow around a construction site while a permanent structure is being constructed.
Di	DITCH			An earth channel or ditch located down, below or across a slope to divert runoff. This may be a temporary or permanent structure.
Dn1	TEMPORARY CONCRETE STRUCTURE			A flexible conduit of heavy-duty fabric or other material designed to safely conduct surface runoff down a slope. This is temporary and non-permanent.
Dn2	PERMANENT CONCRETE STRUCTURE			A paved chute, pipe, sectioned conduit or similar material designed to safely conduct surface runoff down a slope.
Fr	FILTER RIBC			A temporary stone barrier constructed at storm drain inlets and pond outlets.
Gs	GRASS			Rock filter baskets which are hand-placed into position forming soil stabilizing structures.
Gr	GRADE STABILIZATION STRUCTURE			Permanent structures installed to protect stream or waterway where otherwise the slope would be sufficient for the running water to form gullies.
Lv	LEVEL SPREADER			A structure to convert concentrated flow of water into less erosive sheet flow. This should be constructed only on undisturbed soils.
Rd	ROCK FILTER DAM			A permanent or temporary stone filter dam installed across small streams or drainageways.
Re	RETAINING WALL			A wall installed to stabilize cut and fill slopes where minimum permissible slopes are not obtainable. Each situation will require special design.
Rt	RETRO FITTING			A device or structure placed in front of a permanent stormwater detention pond outlet structure to serve as a temporary sediment trap.
Sd1	SEDIMENT BARRIER			A barrier to prevent sediment from leaving the construction site. It may be sandbags, bales of straw or hay, brush, logs and poles, gravel, or a silt fence.
Sd2	INLET SEDIMENT TRAP			An impounding device created by excavating around a storm drain drop inlet. The excavated area will be filled and stabilized on completion of construction activities.
Sd3	TEMPORARY SEDIMENT BASIN			A basin created by excavation or a dam across a waterway. The surface water runoff is temporarily retained during the bulk of the sediment to drop out.
Sd4	TEMPORARY TRAP			A small temporary pond that drains a disturbed area so that sediment can settle out. The principle feature distinguishing a temporary sediment trap from a temporary sediment basin is the lack of a pipe or riser.
Sk	FLOATING SURFACE SHOWER			A burlap device that releases/drains water from the soles of sediment ponds, traps, or basins at a controlled rate of flow.
Sdp	SEEP BERM			Linear control device constructed as a diversion perpendicular to the direction of runoff to enhance dissipation and infiltration, while creating multiple construction channels, the employment of intermediate dikes.
Sr	TEMPORARY STREAM CROSSING			A temporary bridge or culvert-type structure protecting a stream or watercourse from damage by creating construction equipment.
Si	STORMDRAIN OUTLET PROTECTION			A pipe or short section of "grape channel" at the outlet of a storm drain system preventing erosion from the concentrated runoff.
Su	SURFACE ROUGHENING			A rough soil surface with horizontal depressions on a contour or slopes left in a roughened condition after grading.
Tc	TURBIDITY CURTAIN			A floating or stacked barrier installed within the water (it may also be referred to as a floating boom, silt barrier, or silt curtain).
Tp	TOPSOILING			The practice of stripping off the more fertile soil, storing it, then spreading it over the disturbed area after completion of construction activities.
Tr	TREE PROTECTION			To protect desirable trees from injury during construction activity.
Wv	VEGETATED WATERWAY OR STORMWATER CONVEYANCE CHANNEL			Paved or vegetative water outlets for ditches, terraces, berms, dikes or similar structures.

VEGETATIVE PRACTICES

CODE	PRACTICE	DETAIL	MAP SYMBOL	DESCRIPTION
Bf	BUFFER ZONE			Strip of undisturbed original vegetation, enhanced or restored existing vegetation or the reestablishment of vegetation surrounding an area of disturbance or bordering streams.
Cs	CONSTANT VEGETATION WITH VEGETATION			Planting vegetation on dunes that are denuded or critically eroded, or re-wooded.
Ds1	DISTURBED AREA STABILIZATION (NON-SEEDING ONLY)			Establishing temporary protection for disturbed areas where seedling may not have a suitable growing season to produce an erosion reducing cover.
Ds2	DISTURBED AREA STABILIZATION (NON-SEEDING)			Establishing a temporary vegetative cover with fast growing seedlings on disturbed areas.
Ds3	DISTURBED AREA STABILIZATION (NON-SEEDING)			Establishing a permanent vegetative cover such as trees, shrubs, vines, grasses, or legumes on disturbed areas.
Ds4	DISTURBED AREA STABILIZATION (NON-SEEDING)			A permanent vegetative cover using sods on highly erodible or critically eroded lands.
Du	DUST CONTROL ON DISTURBED AREAS			Controlling surface and air movement of dust on construction site, roadway and similar sites.
F-Cd	FLOCCULANTS AND COAGULANTS			Substance formulated to assist in the solid/liquid separation of suspended particles in solution.
Sb	STABILIZATION (NON-SEEDING)			The use of readily available native plant materials to maintain and enhance streambanks, or to prevent, or restore and repair small streambank erosion problems.
Ss	SLOPE STABILIZATION			A protective covering used to prevent erosion and establish temporary or permanent vegetation on steep slopes, shore lines, or channels.
Tac	TERRACES AND BUNDLES			Substance used to anchor straw or hay mats by causing the organic material to bind together.

CHAD R. BRYANT, P.E.
GSWCC LEVEL II
DESIGN PROFESSIONAL
CERTIFICATION # 24596

BRYANT
ENGINEERING

phone: (478) 224-7070 • fax: (478) 224-7072
111 Fernhurst Road, Suite A P.O. Box 1821
Ferry, Georgia 31609

www.bryantengllc.com

COUNTY: HOUSTON
LIC/DISTRICT: 03/5
DWG: 0322-002-MASTER
DATE: 7/16/24
SCALE: 1" = 50'
JOB NO.: 0322-002

THE DRAWING IS THE PROPERTY OF BRYANT ENGINEERING, LLC, AND IS RELEASED AS PRELIMINARY / REVIEW ONLY UNLESS NOTED AS RELEASED FOR CONSTRUCTION. THE USER MAY NOT REPRODUCE OR REUSE WITHOUT EXPRESSED WRITTEN CONSENT.

GEORGIA

EROSION CONTROL NARRATIVE FOR:
PETE'S WAY EXTENSION
CITY OF WARNER ROBINS

REVISIONS	NO.	DATE	DESCRIPTION

SHEET NO.
C-5.4

I. AUTHORIZATION

Any person desiring coverage under this permit as either a Primary Permittee, a Secondary Permittee or a Tertiary Permittee must submit a Notice of Intent (NOI) to the EPD and the NOI must be received by the EPD in accordance with the requirements of Part II, using NOI forms provided by the EPD (or exact photocopy thereof), in order for storm water discharges from construction sites to be authorized. A Notice of Intent for Secondary Permittee coverage can be submitted either concurrently with or after submittal of a Notice of Intent by the Primary Permittee. The Primary Permittee shall provide a copy of the ESDP plan and any subsequent revisions to each Secondary Permittee. Each Secondary Permittee shall sign this sheet in the space provided, acknowledging their receipt of the plan, and the Primary shall retain the signed sheet in their records.

II. ACTIVITIES WITHIN STREAM BUFFERS

1. No construction activities shall be conducted within a 25 ft buffer along the banks of all state waters, as measured horizontally from the point where vegetation has been wrested by normal stream flow or wave action unless it meets an exemption, as defined in 391-3-7-.05 DNR rules on buffer variance procedures and criteria, or without first acquiring the necessary variances and permits.
2. No construction activities shall be conducted within a 50-foot buffer, as measured horizontally from the point where vegetation has been wrested by normal stream flow or wave action, along the banks of any state waters classified as "trout stream" unless it meets an exemption, as defined in 391-3-7-.05 DNR rules on buffer variance procedures and criteria, or without first acquiring the necessary variances and permits.
3. Except as provided above, for buffers required pursuant to (#1 and #2), no construction activities shall be conducted within a buffer and a buffer shall remain in its natural, undisturbed, state of vegetation until all land-disturbing activities on the construction site are completed. Between the time final stabilization of the site is achieved and upon the submittal of a Notice of Termination, a buffer may be thinned or trimmed of vegetation as long as a protective vegetative cover remains to protect water quality and aquatic habitat and a natural canopy is left in sufficient quantity to keep shade on the stream bed.
4. No solid materials, including building materials, shall be discharged to waters of the state, except as authorized by a section 404 permit.
5. Off-site vehicle tracking of dirt, soils, and sediments and the generation of dust shall be eliminated or minimized to the maximum extent practical. A best management practice for this is the use of a construction exit, being a stone stabilized pad located at any point where traffic will be leaving a construction site to a public right-of-way. Geotextile underliners are required to stabilize and support the pad aggregates. The stone aggregate size is 1.5 to 3.5 inches and is to be a minimum pad thickness of 6 inches. Pad width should not be less than 20 feet and should be of sufficient length to perform the function of removing sediment, but no less than 50 feet. Wheels must be cleaned to remove mud prior to entrance onto public rights-of-way.

III. WASHDOWN AREAS 24

1. The discharge of washdown water into stormdrains, streams, rivers, etc. is strictly prohibited.
2. Contractor shall coordinate with site superintendent to excavate a pit deep enough to contain the washdown water.
3. Washdown only tools, concrete mixer chutes, hoppers, and rear of the vehicle. Do not wash out the drum.
4. Contractor shall insure washdown water goes into and stays in the pit. Never allow washdown water to enter a stormdrain.
5. Pit shall be backfilled and smoothed out to proposed grade.
6. If a pit is not accessible, contractor shall washdown into a wheelbarrow or container and carry to a disposal site.

IV. SPILL PREVENTION/SPILL RESPONSE 25

- Equipment Maintenance :** ensure equipment is working properly and free from leaks.
- Material Storage :** the site must contain plastic sheeting or temporary roofs, to cover building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste, and other materials in order to minimize exposure to precipitation and to stormwater. Store containers, drums, and bags away from direct traffic routes, in accordance with manufacturer's recommendations, and in a manner to protect against contamination of storm water.
- POL Spills and Leaks :** minor spills and leaks from construction equipment are a source of potential discharge. Do not use water to clean up spills and dirt from pavements.
- Spill Kits :** have a full-service spill kit on site for minor leaks and drips. Spill kits should include absorbent pads, spill booms, personnel protection equipment, and disposal bags. Once the spill has been confined, use the spill booms to contain the spill. If the pads become saturated, remove them and place them in a safe disposal bag/bin. Any remaining saturated soil or material shall be removed and placed in a safe disposal bag/bin.
- Drip Pan Use During Fueling :** use drip pans and absorbent rags when fueling construction equipment and providing emergency maintenance on equipment. Absorbents are to be handled in accordance with the Resource Conservation and Recovery Act (RCRA) regulations.
- Drip Pan use during vehicle storage :** use drip pans under heavy equipment left idle for two drip pan use during vehicle storage or more calendar days.
- Visual Inspections :** visually inspect construction equipment daily for leaks and spills.
- Hazardous Materials :** store hazardous materials (including fuel) on site in a container with secondary containment (for example, flammable locker). Containers/tanks for fuel (mogas/diesel) should have secondary containment that meets regulatory requirements.
- Protecting Storm Drains :** do not dispose of waste in a storm drain (for example paint, oil, concrete, etc.)
- Vehicle Operation :** do not operate loading equipment. Provide emergency repair to prevent further leaks.

V. STORM WATER SAMPLING 33

- Sampling Requirements.**
- This permit requires the monitoring of nephelometric turbidity in receiving water(s) or outfalls in accordance with this permit. This section is applicable to primary permittees with a total planned disturbance equal to or greater than one (1) acre and tertiary permittees with a total planned disturbance equal to or greater than five (5) acres. This section is not applicable to secondary permittees. The following procedures constitute EPD's guidelines for sampling turbidity.
- a. **Sampling Requirements** shall include the following:
 - (1) A USGS topographic map, a topographic map, or a drawing (referred to as a topographic map) that is a scale equal to or more detailed than a 1:24000 map showing the location of the site or the common development; (a) the location of all perennial and intermittent streams and other water bodies as shown on a USGS topographic map, and all other perennial and intermittent streams and other water bodies located during mandatory field verification, into which the stormwater is discharged; and (b) the receiving water and/or outfall sampling locations. When the permittee has chosen to use a USGS topographic map and the receiving water(s) is not shown on the USGS topographic map, the location of the receiving water(s) must be hand-drawn on the USGS topographic map from where the stormwater(s) enters the receiving water(s) to the point where the receiving water(s) combines with the first blue line stream shown on the USGS topographic map.
 - (2) The analytical method used to collect and analyze the samples including quality control quality assurance procedures. This narrative must include precise sampling methodology for each sampling location;
 - (3) When the permittee has determined that some or all outfalls will be sampled, a rationale must be included on the Plan for the NTU limit(s) selected from Appendix B. This rationale must include the size of the construction site, the calculation of the size of the surface water drainage area, and the type of receiving water(s) (i.e., trout stream or supporting warm water fisheries); and
 - (4) Any additional information EPD determines necessary to be part of the Plan. EPD will provide written notice to the permittee of the information necessary and the time line for submittal.
 - b. **Sample Type.** All sampling shall be collected by "grab samples" and the analyses of these samples must be conducted in accordance with methodology and test procedures established by 40 CFR Part 136 (unless other test procedures have been approved); the guidance document titled "NPDES Storm Water Sampling Guidance Document, EPA 833-B-92-001" and guidance documents that may be prepared by the EPD.
 - (1) Sample containers should be labeled prior to collecting the samples.
 - (2) Samples should be well mixed before transferring to a secondary container.
 - (3) Large mouth, clean and rinsed glass or plastic jars should be used for collecting samples. The jars should be cleaned thoroughly to avoid contamination.
 - (4) Manual, automatic or rising stage samplers may be utilized. Samples required by this permit should be analyzed immediately, but in no case later than 48 hours after collection. However, samples from automatic samplers must be collected no later than the next business day after their accumulation, unless flow through automated analysis is utilized. If automatic sampling is utilized and the automatic sampler is not activated during the qualifying event, the permittee must submit manual sampling or rising stage sampling during the next qualifying event. Dilution of samples is not required. Samples may be analyzed using properly calibrated turbidity meters. Samples are not required to be cooled.
 - (5) Sampling and analysis of the receiving water(s) or outfalls beyond the minimum frequency stated in this permit must be reported to EPD as specified in Part IV.E.
 - c. **Sampling Points.**
 - (1) For construction activities the primary permittee with a total planned disturbance equal to or greater than one (1) acre and tertiary permittee with a total planned disturbance equal to or greater than five (5) acres must sample all receiving water(s), or all outfalls, or a combination of receiving water(s) and outfalls. Samples taken for the purpose of compliance with this permit shall be representative of the monitored activity and the representative of the water quality of the receiving water(s) and/or the stormwater outfalls using the following minimum guidelines:
 - a. The stormwater sample for each receiving water(s) must be taken immediately upstream of the confluence of the first upstream discharge from the permitted activity (i.e., the discharge farthest upstream at the site) but downstream of any other stormwater discharges not associated with the permitted activity. Where appropriate, several upstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the upstream turbidity value.
 - b. The downstream sample for each receiving water(s) must be taken downstream of the confluence of the last stormwater discharge from the permitted activity (i.e., the discharge farthest downstream at the site) but upstream of any other stormwater discharge not associated with the permitted activity. Where appropriate, several downstream samples from across the receiving water(s) may need to be taken and the arithmetic average of the turbidity of these samples used for the downstream turbidity value.
 - c. Ideally the samples should be taken from the horizontal and vertical center of the receiving water(s) or the stormwater outfall channel(s).
 - d. Care should be taken to avoid stirring the bottom sediments in the receiving water(s) or in the outfall stormwater channel.
 - e. The sampling container should be held so that the opening faces upstream.
 - f. The samples should be kept free from floating debris.
 - g. Permittees do not have to sample sheet flow that flows onto undisturbed natural areas or areas stabilized by permanent structures and areas located outside the waste disposal limits of a landfill cell that has been certified by EPD for waste disposal, 100% of the soil surface is uniformly covered in permanent vegetation with a density of 70% or greater, or landscaped according to the Plan (uniformly covered with landscaping materials in planned landscaped areas), or equivalent permanent stabilization measures as defined in the Manual (excluding a crop of annual vegetation and seeding of target crop perennials appropriate for the region).
 - h. All sampling pursuant to this permit must be done in such a way (including generally accepted sampling methods, locations, timing, and frequency) as to accurately reflect whether stormwater runoff from the construction site is in compliance with the standard set forth in Parts III.D.3. or III.D.4., whichever is applicable.

VI. INSPECTIONS & RECORD KEEPING 30

- Primary Permittee.**
- (1) Each day when any type of construction activity has taken place at a primary permittee's site, certified personnel provided by the primary permittee shall inspect: (a) all areas at the primary permittee's site where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment and (b) all locations at the primary permittee's site where vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termination is submitted.
 - (2) Measure and record rainfall within disturbed areas of the site that have not met final stabilization once every 24 hours except any non-working Saturday, non-working Sunday and non-working Federal holiday. The data collected for the purpose of compliance with this permit shall be representative of the monitored activity. Measurement of rainfall may be suspended if all areas of the site have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region.
 - (3) Certified personnel (provided by the primary permittee) shall inspect the following at least once every seven (7) calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first):
 - a. disturbed areas of the primary permittee's construction site; (b) areas used by the primary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the primary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.a.(4). These inspections must be conducted until a Notice of Termination is submitted.
 - (4) Certified personnel (provided by the primary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is submitted to EPD) the areas of the site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s).
 - (5) Based on the results of each inspection, the site description and the pollution prevention and control measures identified in the Erosion, Sedimentation and Pollution Control Plan, the Plan shall be revised as appropriate not later than seven (7) calendar days following each inspection. Implementation of such changes shall be made as soon as practical but in no case later than seven (7) calendar days following each inspection. The primary permittee must amend the Plan in accordance with Part IV.D.4.b.(5), when a secondary permittee notifies the primary permittee of any Plan deficiencies.
 - (6) A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.a.(5), of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site or that portion of a construction site that has been phased has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify an incident, the inspection report shall contain a statement that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit.
- Secondary Permittee.**
- (1) Each day when any type of construction activity has taken place at a secondary permittee's site, certified personnel provided by the secondary permittee shall inspect: (a) all areas used by the secondary permittee where petroleum products are stored, used, or handled for spills and leaks from vehicles and equipment; and (b) all locations at the secondary permittee site where that permittee's vehicles enter or exit the site for evidence of off-site sediment tracking. These inspections must be conducted until a Notice of Termination is submitted. This paragraph is not applicable to utility companies and utility contractors if they are secondary permittees.
 - (2) Certified personnel (provided by the utility companies and utility contractors if they are secondary permittees) shall inspect the following each day any type of construction activity has taken place at the construction site: (a) areas of the construction site disturbed by the utility companies and utility contractors that have not undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region; (b) areas used by the utility companies and utility contractors for storage of materials that are exposed to precipitation that have not undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region or established a crop of annual vegetation and a seeding of target perennials appropriate for the region; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the utility companies and utility contractors' construction activities shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). This paragraph is not applicable to utility companies and utility contractors when they are secondary permittees performing service line installations or when conducting repairs on existing line installations.
 - (3) Certified personnel (provided by the secondary permittee) shall inspect the following at least once every seven calendar days and within 24 hours of the end of a storm that is 0.5 inches rainfall or greater (unless such storm ends after 5:00 PM on any Friday or on any non-working Saturday, non-working Sunday or any non-working Federal holiday in which case the inspection shall be completed by the end of the next business day and/or working day, whichever occurs first): (a) disturbed areas of the secondary permittee's construction site; (b) areas used by the secondary permittee for storage of materials that are exposed to precipitation; and (c) structural control measures. Erosion and sediment control measures identified in the Plan applicable to the secondary permittee's site shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). For areas of a site that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region, the permittee must comply with Part IV.D.4.b.(4). These inspections must be conducted until a Notice of Termination is submitted. This paragraph is not applicable to utility companies and utility contractors if they are secondary permittees.
 - (4) Certified personnel (provided by the secondary permittee) shall inspect at least once per month during the term of this permit (i.e., until a Notice of Termination is submitted to EPD) the areas of their sites that have undergone final stabilization or established a crop of annual vegetation and a seeding of target perennials appropriate for the region. These areas shall be inspected for evidence of, or the potential for, pollutants entering the drainage system and the receiving water(s). Erosion and sediment control measures identified in the Plan shall be observed to ensure that they are operating correctly. Where discharge locations or points are accessible, they shall be inspected to ascertain whether erosion control measures are effective in preventing significant impacts to receiving water(s). This paragraph is not applicable to utility companies and utility contractors if they are secondary permittees.
 - (5) Based on the results of each inspection, the secondary permittee must notify the primary permittee within 24-hours of any suspected BMP design deficiencies. The primary permittee must evaluate whether these deficiencies exist within 48 hours of notice of them and if these deficiencies are found to exist must amend the Plan in accordance with Part IV.C. of this permit to address those deficient BMPs within seven (7) days of being notified by the secondary permittee. When the Plan is amended, the primary permittee must notify and provide a copy of the amendment to all affected secondary permittee(s) within this seven (7) day period. The secondary permittees must implement any new Plan requirements affecting their site(s) within 48-hours of notification by the primary permittee.
 - (6) A report of each inspection that includes the name(s) of certified personnel making each inspection, the date(s) of each inspection, construction phase (i.e., initial, intermediate or final), major observations relating to the implementation of the Erosion, Sedimentation and Pollution Control Plan, and actions taken in accordance with Part IV.D.4.b.(5), of the permit shall be made and retained at the site or be readily available at a designated alternate location until the entire site has undergone final stabilization and a Notice of Termination is submitted to EPD. Such reports shall be readily available by the end of the second business day and/or working day and shall identify all incidents of best management practices that have not been properly installed and/or maintained as described in the Plan. Where the report does not identify any incidents, the inspection report shall contain a certification that the best management practices are in compliance with the Erosion, Sedimentation and Pollution Control Plan. The report shall be signed in accordance with Part V.G.2. of this permit. This paragraph is not applicable to utility companies and utility contractors if they are secondary permittees performing only service line installations or when conducting repairs on existing line installations.

VII. RETENTION OF RECORDS 32

- F. Retention of Records.**
1. The Primary Permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate location from commencement of construction until such time as a NOT is submitted in accordance with Part VI:
 - a. A copy of all Notices of Intent submitted to EPD;
 - b. A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit;
 - c. The design professional's report of the results of the inspection conducted in accordance with Part IV.A.5. of this permit;
 - d. A copy of all sampling information, results, and reports required by this permit;
 - e. A copy of all inspection reports generated in accordance with Part IV.D.4.a. of this permit;
 - f. A copy of all violation summaries and violation summary reports generated in accordance with Part III.D.2. of this permit; and
 - g. Daily rainfall information collected in accordance with Part IV.D.4.a.(2), of this permit.
 2. Each secondary permittee shall retain the following records at the construction site or the records shall be readily available at a designated alternate location from commencement of construction until such time as a NOT is submitted in accordance with Part VI:
 - a. A copy of all Notices of Intent submitted to EPD;
 - b. A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit or the applicable

VIII. RETENTION OF RECORDS (cont.) 32

- a. A copy of the Erosion, Sedimentation and Pollution Control Plan required by this permit or the applicable portion of the Erosion, Sedimentation and Pollution Control Plan for their activities at the construction site required by this permit;
 - b. A copy of all inspection reports generated in accordance with Part IV.D.4.b. of this permit; and
 - c. A copy of all violation summaries and violation summary reports generated in accordance with Part III.D.2. of this permit.
3. Copies of all Notices of Intent, Notices of Termination, inspection reports, sampling reports (including all calibration and maintenance records and all original strip chart recordings for continuous monitoring instrumentation) or other reports requested by the EPD, Erosion, Sedimentation and Pollution Control Plans, records of all data used to complete the Notice of Intent to be covered by this permit and all other records required by this permit shall be retained by the permittee who either produced or used it for a period of at least three years from the date that the NOT is submitted in accordance with Part VI. of this permit. These records must be maintained at the permittee's primary place of business or at a designated alternative location once the construction activity has ceased at the permitted site. This period may be extended by request of the EPD at any time upon written notification to the permittee.


VIII. SAMPLING FREQUENCY & REPORTING OF SAMPLING RESULTS 31

- d. **Sampling Frequency.**
 - (1) The Primary Permittee must sample in accordance with the Plan at least once for each rainfall event described below. For a qualifying event, the permittee shall sample at the beginning of any stormwater discharge to a monitored receiving water and/or from a monitored outfall location within in forty-five (45) minutes or as soon as possible.
 - (2) However, where manual and automatic sampling are impossible (as defined in this permit), or are beyond the permittee's control, the permittee shall take samples as soon as possible, but in no case more than twelve (12) hours after the beginning of the stormwater discharge.
 - (3) Sampling by the permittee shall occur for the following qualifying events:
 - (a) For each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours as defined in this permit after all clearing and grubbing operations have been completed, but prior to completion of mass grading operations, in the drainage area of the location selected as the sampling location;
 - (b) In addition to (a) above, for each area of the site that discharges to a receiving water or from an outfall, the first rain event that reaches or exceeds 0.5 inch with a stormwater discharge that occurs during normal business hours as defined in this permit either 90 days after the first sampling event or after all mass grading operations have been completed, but prior to submittal of a NOT, in the drainage area of the location selected as the sampling location, whichever comes first;
 - (c) At the time of sampling performed pursuant to (a) and (b) above, if BMPs in any area of the site that discharges to a receiving water or from an outfall are not properly designed, installed and maintained, corrective action shall be defined and implemented within two (2) business days, and turbidity samples shall be taken from discharges from that area of the site for each subsequent rain event that reaches or exceeds 0.5 inch during normal business hours" until the selected turbidity standard is attained, or until post-storm event inspections determine that BMPs are properly designed, installed and maintained;
 - (d) Where sampling pursuant to (a), (b) or (c) above is required but not possible (or not required because there was no discharge), the permittee, in accordance with Part IV.D.4.a.(6), must include a written justification in the inspection report of why sampling was not performed. Providing this justification does not relieve the permittee of any subsequent sampling obligations under (a), (b) or (c) above; and
 - (e) Existing construction activities, i.e., those that are occurring on or before the effective date of this permit, that meet the sampling required by (a) above shall sample in accordance with (b). Those existing construction activities that have met the sampling required by (b) above shall not be required to conduct additional sampling other than as required by (c) above.
 - *Note that the permittee may choose to meet the requirements of (a) and (b) above by collecting turbidity samples from any rain event that reaches or exceeds 0.5 inch and allows for sampling at any time of the day or week.
7. **Non-stormwater discharges.** Except for flows from fire fighting activities, sources of non-stormwater listed in Part III.A.2. of this permit that are combined with stormwater discharges associated with construction activity must be identified in the Plan. The Plan shall identify and ensure the implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the discharge.
- E. Reporting.**
1. The applicable permittees are required to submit the sampling results to the EPD at the address shown in Part I.I.C. by the fifteenth day of the month following the reporting period. Reporting periods are months during which samples are taken in accordance with this permit. Sampling results shall be in a clearly legible format. Upon written notification, EPD may require the applicable permittee to submit the sampling results on a more frequent basis. Sampling and analysis of any stormwater discharge(s) or the receiving water(s) beyond the minimum frequency stated in this permit must be reported in a similar manner to the EPD. The sampling reports must be signed in accordance with Part V.G.2. Sampling reports must be submitted to EPD using the electronic submittal service provided by EPD. Sampling reports must be submitted to EPD until such time as a NOT is submitted in accordance with Part VI.
 2. All sampling reports shall include the following information:
 - a. The rainfall amount, date, exact place and time of sampling or measurements;
 - b. The name(s) of the certified personnel who performed the sampling and measurements;
 - c. The date(s) analyses were performed;
 - d. The time(s) analyses were initiated;
 - e. The name(s) of the certified personnel who performed the analyses;
 - f. References and written procedures, when available, for the analytical techniques or methods used;
 - g. The results of such analyses, including the bench sheets, instrument readouts, computer disks or tapes, etc., used to determine these results;
 - h. Results which exceed 1000 NTU shall be reported as "exceeds 1000 NTU;" and
 - i. Certification statement that sampling was conducted as per the Plan.
 3. All written correspondence required by this permit shall be submitted by return receipt certified mail (or similar service) to the appropriate District Office of the EPD according to the schedule in Appendix A of this permit. The permittee shall retain a copy of the proof of submittal at the construction site or the proof of submittal shall be readily available at a designated location from commencement of construction until such time as a NOT is submitted in accordance with Part VI.

IX. EROSION CONTROL/NPDES CERTIFICATION STATEMENT

- 12 (1) "I CERTIFY UNDER PENALTY OF LAW THAT THIS PLAN WAS PREPARED AFTER A SITE VISIT TO THE LOCATIONS DESCRIBED HEREIN BY MYSELF OR MY AUTHORIZED AGENT, UNDER MY SUPERVISION."
 - 13 (2) "I CERTIFY THAT THE PERMITTEE'S EROSION, SEDIMENTATION AND POLLUTION CONTROL PLAN PROVIDES FOR AN APPROPRIATE AND COMPREHENSIVE SYSTEM OF BEST MANAGEMENT PRACTICES REQUIRED BY THE GEORGIA WATER QUALITY CONTROL ACT AND THE DOCUMENT "MANUAL FOR EROSION AND SEDIMENT CONTROL IN GEORGIA" (MANUAL) PUBLISHED BY THE GEORGIA SOIL AND WATER CONSERVATION COMMISSION AS OF JANUARY 1 OF THE YEAR IN WHICH THE LAND-DISTURBING ACTIVITY WAS PERMITTED, PROVIDES FOR THE SAMPLING OF THE RECEIVING WATER(S) OR THE SAMPLING OF THE STORMWATER OUTFALLS AND THAT THE DESIGNED SYSTEM OF BEST MANAGEMENT PRACTICES AND SAMPLING METHODS IS EXPECTED TO MEET THE REQUIREMENTS CONTAINED IN THE GENERAL NPDES PERMIT NO. GAR100001."
- Chad R. Bryant* 24596
- GSWCC LEVEL II DESIGN PROFESSIONAL CERTIFICATION #

X. USGS QUADRANGLE MAP 35



XI. DESCRIPTION OF RECEIVING WATERS 11		XII. CRITICAL ADJACENT AREAS		XIII. APPENDIX B RATIONALE 34									
THE RECEIVING WATERS FOR THIS SITE IS SANDY RUN CREEK. THIS CREEK IS A "BLUE-LINE STREAM" ON THE MOST RECENT USGS QUADRANGLE MAP AND SUPPORTS WARM WATER FISHERIES. THIS SITE IS LOCATED AT LATITUDE N32.601652". LONGITUDE W83.727704". 9.69 ACRES WILL BE DISTURBED.		No residential areas, lakes, wetlands, or streams will be affected by the proposed development nor are any adverse impacts expected due to the proposed development.		Site Size		Surface Water		Drainage Area, square miles					
				Acres	0-9	5-9.99	10-24.99	25-49.99	50-99.99	100-249.99	250-499.99	500+	
1.0-10		75		150	200	400	750	750	750	750	750	750	
10.01-25		50		100	100	200	300	500	750	750	750	750	
25.01-50		50		50	100	100	100	200	300	750	750	750	
50.01-100		50		50	50	100	100	150	300	600	600	600	
		50		50	50	50	50	100	200	200	200	200	

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.














THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.

THIS SITE DOES NOT DISCHARGE STORM WATER INTO AN IMPAIRED STREAM SEGMENT, OR WITHIN 1 LINEAR MILE UPSTREAM OF AND WITHIN THE SAME WATERSHED AS ANY PORTION OF A BOTA IMPAIRED STREAM SEGMENT.



- To protect the soil surface from erosion
- To reduce damage from sediment and runoff to down-stream areas
- To improve wildlife habitat and visual resources
- To improve aesthetics

REQUIREMENT FOR REGULATORY COMPLIANCE

This practice shall be applied immediately to rough graded areas that will be undisturbed for longer than six months. This practice or sodding shall be applied immediately to all areas at final grade. **Final Stabilization** means that all soil disturbing activities at the site have been completed, and that for the remainder of the project, no areas not covered by permanent structures and areas located outside the waste disposal limits of a landfill cell that has been certified by the GA EPD for waste disposal, 100% of the soil surface is uniformly covered in permanent vegetation with a density of 70% or greater, or landscaped areas that are not uniformly covered with landscaping materials in planned landscaped areas), or equivalent permanent stabilization measures.

GSWCC 2016 Edition

6-35



PURPOSE

- To prevent surface and air movement of dust from exposed soil surfaces.

CONDITIONS
This practice is applicable to areas subject to surface and air movement of dust where on and off-site damage may occur without treatment.

METHOD AND MATERIALS

A. Temporary Methods

Mulches. See standard **Ds1 - Disturbed Area Stabilization (With Mulching Only)**. Synthetic resins may be used instead of asphalt to bind mulch material. Refer to specification **Tac - Tackifiers**. Resins should be used according to manufacturer's recommendations.

Spray-on Adhesives. These are used on mineral soils (not effective on muck soils). Keep traffic out of these areas. Refer to specification **Tac - Tackifiers**.

Tillage. This practice is designed to roughen and bring clods to the surface. It is an emergency

measure that should be used before wind erosion starts. Begin plowing on windward side of site. Chisel-type plows spaced about 12 inches apart, spring-toothed harrows, and similar plows are examples of equipment that may produce the desired effect.

Irrigation. This is generally done as an emergency treatment. Site is sprinkled with water until the surface is wet. Repeat as needed.

Barriers. Solid board fences, snowfences, burlap fences, crate walls, bales of hay and similar material can be used to control air currents and soil blowing. Barriers placed at right angles to prevailing currents at intervals of about 15 times their height are effective in controlling wind erosion.


Calcium Chloride. Apply at rate that will keep surface moist. May need retreatment.

B. Permanent Methods

Permanent Vegetation. See specification Ds3-**Disturbed Area Stabilization (With Permanent Vegetation)**. Existing trees and large shrubs may afford valuable protection if left in place.

Topsoiling. This entails covering the surface with less erosive soil material. See specification **Tp - Topsoiling**.

Stone. Cover surface with crushed stone or coarse gravel. See specification **Cr-Construction Road Stabilization**.




NOTE: BASED ON THE VOLUME OF SEDIMENT GENERATED BY THIS SITE, THE SEDIMENT SHALL BE REMOVED FROM THE PONDS ANNUALLY. HOWEVER, SEDIMENT SHALL ALSO BE REMOVED WHEN THE SEDIMENT REACHES THE BASE OF THE SEDIMENT GAGE, WHEN WATER LEVELS PREVENT THE VISUAL INSPECTION OF SEDIMENT, THE OPERATOR SHALL USE THE RED STRIP ON THE SEDIMENT GAGE AS AN INDICATOR. IF THE WATER LEVEL STAYS ABOVE THE RED STRIPE FOR MORE THAN 60 DAYS, THEN THE SEDIMENT SHALL BE REMOVED.

SILT GA
N.T.S.

PLEASE NOTE


DETAILS SHOWN ON THIS SHEET ARE STANDARD EROSION CONTROL PRACTICES USED IN THIS GEOGRAPHIC LOCATION. ALL EROSION CONTROL PRACTICES SHOWN MAY NOT BE USED DURING CONSTRUCTION ACTIVITIES. THESE DETAILS HAVE BEEN PROVIDED FOR THE CONTRACTOR TO MANAGE ANY UNFORESEEN EROSION PROBLEMS THAT MAY OCCUR DURING PHASED CONSTRUCTION ACTIVITIES. PLEASE REFER TO THE EROSION CONTROL PLAN FOR ALL PRACTICES REQUIRED FOR THIS PROJECT, ANY DESIGN CHANGES OR ADDITIONS SHOULD BE COORDINATED WITH THE DESIGN ENGINEER.





1. TRENCH SHALL BE EXCAVATED TO THE DEPTH REQUIRED PROVIDING A UNIFORM AND CONTINUOUS BEARING AND SUPPORT FOR THE PIPE ON SOLID, UNDISTURBED GROUND AT EVERY POINT BETWEEN BELLS OR COUPLINGS.
2. REQUIRED COMPACTING AND TESTING
 1. OUTSIDE OF PAVED OR PROPOSED PAVED AREAS, COMPACTED TO 95% STANDARD PROCTOR.
 2. UNDER PAVED OR PROPOSED PAVED AREAS, COMPACTED TO 100% STANDARD PROCTOR.
 3. UNDER D.O.T. ROADWAYS OR PROPOSED D.O.T. ROADWAYS, COMPACTED TO 100% STANDARD PROCTOR.
4. ALL COMPACTING TESTING SHALL BE CONDUCTED BY AN APPROVED SOILS' TESTING FIRM.

DETAIL - WATER LINE BEDDING
N.T.S.



DETAIL - TYPICAL FIRE HYDRANT SETTING
N.T.S.

X	C	D
4"	8"	1'- 6"
6"	10"	1'- 9"
8"	12"	2'- 0"
10"	14"	2'- 6"
12"	16"	3'- 0"

NOTE:

150 P.S.I. TEST PRESSURE
SOIL BORING OF 2000 P.S.F.
3000 P.S.I. CONCRETE

ALL C AND D'S HAVE MIN. OF 1'- 0"



1. ALL FITTINGS SHALL BE PROPERLY BLOCKED OR TIE-RODDED AS REQUIRED TO INSURE SUFFICIENT ANCHORAGE OF THE PIPING.
2. PROVIDE SUFFICIENT BACKFILL AND COMPACTION OVER WATER LINE TO ASSURE PROTECTION OF THE PIPE.

WATER MAIN
CONFLICT DETAIL
N.T.S.



1. ALL BEARING SURFACES TO BE CARRIED TO UNDISTURBED SOIL
2. THESE TABLES SHOW MINIMUM SIZE THRUST BLOCKS FOR A SOIL BEARING PRESSURE OF 2,000 P.S.I. AND AN INTERNAL PRESSURE OF 150 P.S.I.
3. WHEN POOR SOIL (SILT, CLAY, MUCK, PEAT, ETC.) ARE ENCOUNTERED, SUBMIT DETAILS OF AN ALTERNATIVE SYSTEM TO THE PROJECT ENGINEER FOR APPROVAL.


DETAIL - THRUST BLOCKS FOR PLUGS
N.T.S.





NOTE:


1. PROTECTIVE COATING SHALL BE STRIPPED PRIOR TO SPLICE. WRAP FINISHED SPLICE WITH ELECTRICAL TAPE.

DETAIL - TRACER WIRE PLACEMENT (WATER)
N.T.S.






TYPICAL PAVING DETAIL
HEAVY DUTY
N.T.S.




DETAIL - TYPICAL MANHOLE PLAN
N.T.S.

"A"	"B"	"C"	"D"	"E"	"F"	"G"	"H"
12"	4'-2"	6'-6"	2'-6"	1'-8"	1'-2"	1'-3"	1'-7"
15"	4'-6"	6'-10"	2'-10"	2'-0"	1'-3"	1'-3"	1'-7"
18"	4'-10"	7'-2"	3'-2"	2'-4"	1'-4"	1'-3"	1'-7"
24"	5'-4"	7'-8"	3'-8"	2'-10"	1'-5"	1'-4"	2'-1"
30"	6'-0"	8'-4"	4'-4"	3'-6"	1'-9"	1'-6"	2'-5"
36"	6'-6"	8'-10"	4'-10"	4'-0"	2'-0"	1'-8"	2'-11"
3'-36"	17'-6"	19'-10"	4'-10"	4'-0"	2'-0"	1'-8"	2'-11"
42"	7'-0"	9'-4"	5'-4"	4'-6"	2'-3"	2'-0"	3'-6"
48"	7'-8"	10'-0"	6'-0"	5'-2"	2'-6"	2'-0"	4'-0"
54"	8'-3"	10'-2"	6'-7"	5'-9"	2'-9"	2'-0"	4'-6"
60"	8'-10"	11'-2"	7'-2"	6'-4"	3'-0"	2'-2"	5'-0"
5'-60"	31'-4"	33'-8"	7'-2"	6'-4"	3'-0"	2'-2"	5'-0"
6'-60"	38'-10"	41'-2"	7'-2"	6'-4"	3'-0"	2'-2"	5'-0"

DETAIL - CONCRETE HEADWALL
N.T.S.



TYPICAL SECTION FOR 120' R/W
N.T.S.



TURF REINFORCEMENT MATTING (TRM)

- NOTES:
1. INSTALL PER MANUFACTURER'S RECOMMENDATION.
 2. OVERLAP ADJACENT ROLLS A MINIMUM OF 3" OR MORE IF RECOMMENDED BY MANUFACTURER. INSTALL ANCHORS ON OVERLAP SEAM AT A MAXIMUM OF EVERY 18".
 3. LAY TRM LOOSE TO MAINTAIN DIRECT CONTACT WITH SOIL.
 4. SECURE TRM TO GROUND SURFACE USING U-SHAPED WIRESTAPLES SPACED AT 2 PER SQUARE YARD. REFER TO MANUFACTURER'S RECOMMENDATION FOR WIRE STAPLE SPACING PATTERN.